

OPPORTUNITIES AND CHALLENGES FOR STRUCTURAL ENGINEERING OF DIGITALLY FABRICATED CONCRETE

Costantino Menna^{1*}, Jaime Mata-Falcón², Freek Bos³, Gieljan Vantghem⁴, Liberato Ferrara⁵, Domenico Asprone¹, Theo Salet³, Walter Kaufmann²

¹ Department of Structures for Engineering and Architecture, University of Napoli Federico II - Naples, Italy

² Institute of Structural Engineering, ETH - Zurich, Switzerland

³ Department of the Built Environment, Eindhoven University of Technology - Eindhoven, Netherlands

⁴ Department of Structural Engineering and Building Materials, Ghent University - Ghent, Belgium

⁵ Department of Civil and Environmental Engineering, Politecnico di Milano – Milan, Italy

Abstract

Digital fabrication technologies utilizing concrete (DFC) have recently enabled form freedom for the production of a variety of concrete-made objects having mainly architectural and aesthetic functions. Structural elements or civil/building structures made by DFC demonstrate a high engineering potential, mainly for tailoring the final shape while optimising the structural/functional performance, material use, overall costs, and architectural effectiveness. However, the design of structurally efficient DFC constructions or components is often faced with a lack of a common structural engineering approach that can adapt to specific DFC particularities.

In this paper, we provide a systematic overview of a number of DFC structural projects developed thus far. A comprehensive discussion about structural engineering details is provided, addressing the related fundamental structural issues and envisioning opportunities and challenges toward achieving the full potential of DFC.

Keywords

Digital Fabrication with Concrete; Structural Engineering; Construction Projects; Design with DFC.

1. INTRODUCTION

In recent years, advances in computational design tools and industrial automation have allowed architects and engineers to carry out construction projects characterised by an increasing overall complexity and a high level of digitalisation [1–5]. The growing number of irregular-shape buildings or structures recently constructed, or planned in various countries, represents the evidence of technological progress characterised by an evolution of conventional construction materials, design approaches, and manufacturing methods. In this context, digital fabrication is becoming a valuable approach to overcome the existing manufacturing limitations, as it can transform digital design into physical products [6] by adopting one or more materials (polymers, steel, wood, clay, etc.) and different automated processes (e.g. robotic assembly, extrusion, lamination, and additive manufacturing).

Different advantages are potentially offered for the specific construction project wherein digital fabrication is implemented [7–9]. Besides a higher degree of customisation, the positive performance of a digitally fabricated system can be evaluated by monitoring four main factors: time, cost, quality, and flexibility [10]. In other words, removing the formworks in favour of modularisation and prefabrication or part of the concrete/reinforcement due to material [11, 12] and shape efficiency [13] results in cost and CO₂ emission reduction [2]14], while providing additional functions [15, 16]; the resulting features represent, in practice, the key decision-making factors for the overall construction management of the project [6, 17]. However, this scenario has to deal with the slow innovation uptake of the construction industry even if estimates for future investments in infrastructure [18] have stimulated this sector toward the transformation of the way in which numerous engineering and construction firms operate [19].

A recent review by Austern *et al.* [20] classified the appearance of digital fabrication projects in the available literature, noting the implementation of approximately 15 different automated processes adopting more than 10 different materials. All of these fabrication techniques inevitably introduce feasibility and affordability issues, which often force engineers and architects to adjust the design itself according to the constraints arising from the new processes. These constraints can be grouped into the following four main categories:

- fabrication constraints (e.g. limitations associated with the available machine capabilities and the size compared to that in the manufacturing industry),
- material constraints (e.g. process-dependent physical and mechanical properties and durability),
- construction constraints (e.g. ease of assembly and transportation), and
- design constraints (e.g. code compliance and geometry).

Currently, wood, steel, polymers, and concrete are the materials mostly adopted in digital fabrication applied to construction projects [20]. Among these, polymers have the lowest prevalence and their use for the fabrication of building components is limited because of the high manufacturing cost and low stiffness [21]. In contrast, robotic systems represent a mature technology for the fabrication of non-standard timber structures, being able to obtain automatic joinery [22] as well as large-scale assembly by adopting new computational approaches [23]. A real-world case is that of the ‘The Sequential Roof’ project developed at ETH Zurich [24] and manufactured by implementing a custom six-axis overhead gantry robot (see Figure 1a). To guarantee compliance with building regulations,

1 real-scale specimens were subjected to mechanical load testing. In contrast, steel-based structures are
2 generally digitally fabricated using powder bed fusion and directed energy deposition processes [21].
3 Large-scale applications have been implemented, for instance, in the MX3D project [25], aimed to
4 3D print an 8-m stainless steel bridge (a footbridge across the Oudezijds Achterburgwal canal) with
5 a gas metal arc welding-based six-axis industrial robot (see Figure 1b). In this case, experimental tests
6 were needed to characterise the structural behaviour for ensuring the compliance with building
7 regulations [26].



8 Figure 1: (a) ‘The Sequential Roof’ project developed at ETH Zurich [24] and (b) MX3D project [25].
9

10 Apart from wood and steel, concrete and cement-based materials have been increasingly used in
11 digital fabrication techniques in the last 5–10 years. In a recent study by Tay *et al.* [14] reporting an
12 analysis of the variants of concrete printing processes published worldwide over the last twenty years,
13 the researchers found that topic-related research works almost doubled in the years 2013–2016
14 compared to in the previous 16 years. Further, automated manufacturing techniques are collectively
15 identified as digital fabrication with concrete (DFC), allowing the construction of both structural and
16 non-structural products (to a greater or lesser extent) without the use of traditional formworks.

17 The implementation of the different DFC methods is currently capable of producing architectural
18 items, load bearing and non-load bearing building/infrastructure components, and full-scale
19 houses/structures; an explicit mapping of the resulting digitally fabricated systems’ characteristics is
20 provided in [27], whereas the variety of available methods can be generally grouped on the basis of
21 [14, 28, 29]:

- 22 • **Process:** (i) **extrusion process** in which concrete is automatically placed layer-by-layer
23 through a moving nozzle, following a predefined digital path reproduced by Cartesian gantry,
24 robotic, crane, or cable robot systems [30–33]; (ii) **formwork printing** in which concrete or
25 other materials are used to fill a digitally fabricated formwork [34]; (iii) **use of temporary**
26 **supports** which are digitally designed against applied loads, fabricated, and then,
27 subsequently concreted [35]; (iv) **slipforming** consisting of a vertically moving formwork in
28 which concrete is placed in the fluid state and allowed to harden in a controlled manner to
29 fabricate variable cross-sectional area structures (e.g. the smart dynamic casting system
30 developed by Lloret *et al.* [36, 37]); (v) **particle bed 3d printing** (also known as ‘selective
31 binding’ or ‘binder jetting’) which is based on the selective and automated deposition of a
32 binder onto a layer of particles (e.g. see [38]). This process is also referred to as particle bed
33 fusion [28]; however, as it does not involve the melting of a material, the more general term
34 of particle bed 3d printing, previously mentioned should be preferred; and (vi) **hybrid**
35 **techniques** which aim to introduce hybrid construction concepts by using the available

1 fabrication processes or reinforcement (e.g. sparse concrete reinforcement in meshworks
2 which combines robot-based 3D concrete printing and textile reinforcement meshes [39] or
3 shotcrete 3D printing which is based on an automated shotcreteing process with the ability to
4 integrate structural reinforcement [40]).

- 5 • *Fabrication site*: (i) **on-site construction** is the production of full houses/structures in an open
6 environment by means of machinery larger (e.g. the use of a gantry printer in DCP [41]) or
7 even smaller (e.g. in-situ fabricator of mesh mould process [42]) than the structure being
8 fabricated; and (ii) **prefabrication** is a more robust fabrication process enclosed in a
9 controlled environment which produces components/subassemblies at the structural scales
10 (but not entire structures) with a higher quality level [42, 43].

11 The recent successful implementation of such DFC methods demonstrates their potential in achieving
12 concrete structures of complex geometry [45], such as thin and stable shells, arches, lightweight forms
13 with complex topologies, advanced modular structures, custom concrete stairs [46], and even
14 promising solutions for the construction of human settlements on other celestial bodies such as the
15 Moon and Mars [47]. However, this revolutionary shift has introduced new possibilities and
16 constraints for the design, dimensioning, detailing, and production of structures [48]. Indeed, it is
17 necessary to focus on a systematic approach to address the new technological constraints that have
18 turned into interlinked engineering challenges acting on multiple levels of implementation.

19 At the material level, depending on the specific DFC method adopted, new requirements have been
20 introduced for the fresh concrete state because of the considerable changes compared to the standard
21 formative processes. In particular, the rheological and mechanical properties of the growing object
22 give rise to new fabrication issues such as pumpability, buildability, printability, extrudability, and
23 fluid infiltration capability into the particle bed [38, 48–50]. Moreover, the mix-design solutions
24 adopted thus far have introduced new performances in the hardened state, making the digitally
25 fabricated concrete objects remarkably different from those obtained using the well-established
26 formative process. In addition, the additive nature of many DFC techniques yields layered structures
27 with a significant anisotropy with regard to strength (occurring in both the vertical and the horizontal
28 directions) rather than stiffness. The interfaces between adjacent layers generated by additive DFC
29 processes are typically characterised by reduced bond strengths (in both the shear and the normal
30 directions) and are commonly referred to as weak layer interfaces, cold joints or lift lines [40, 51]: a
31 number of factors related to the combination of a specific DFC process and material composition (e.g.
32 print head speed, print nozzle height, resting time, and moisture content) have been shown to have
33 quantitative effects on the interface properties, leading, in some cases, to a 50% or higher reduction
34 as compared to the bulk specimens [53]. Similar considerations can be drawn for other DFC
35 processes, such as particle bed 3d printing, in which the compressive strength of the printed cylinders
36 has been shown to depend on the penetration ratio of the binder [38].

37 Moving to full-scale construction projects with DFC, it is clear that all the above-mentioned
38 mechanical aspects characterising the hardened state may represent an evident obstacle for DFC to
39 reach maturity. In addition, unless compressed structures are considered, a key point to note is that
40 the implementation of digitally fabricated concrete structures is made possible only in combination
41 with reinforcement resisting tensile forces, which overcome the lack of sufficient tensile capacity and
42 ductility of cementitious materials. Reinforcement concepts and principles are currently adapting to
43 the different DFC processes [54]. This progressive change will affect the reinforcement technology

(e.g. the various implementation techniques of fibres, rebar, rods, and filaments in DFC processes), dimensioning, and detailing in contrast to the conventional concrete constructions.

In this review paper, we aim to first provide the information collected on the existing documented DFC construction projects, bringing out the structural engineering aspects behind their design and execution. Then, a discussion is provided to address the common structural characteristics and issues associated with the DFC particularities described in the paper; in particular, being the extrusion process one of the most widely used and documented DFC technique, most of the discussion outcomes will be related to that technique. The current stage of development, in terms of the existing building regulations and full-scale validation testing, is also reported in this review, representing a key step toward the development of a common understanding of such an interdisciplinary topic.

11

2. AVAILABLE (DOCUMENTED) STRUCTURAL APPLICATIONS OF DFC

After an initial phase of realisation of showcase projects (e.g. [55–57]), DFC is now being introduced into general-use structures such as short-span bridges, whole buildings printed in full, and stand-alone structures; see Table 1 and references therein. While the catalogue of examples held only a handful of projects two to three years ago, it is now expanding rapidly and will continue to do so judging by the number of announced projects [58–60]. Unfortunately, thus far, publicly available documentation on structural engineering has been extremely scarce.

Asprone *et al.* [61] noted that the application of DFC in the production and construction of structures affects each of the pillars of its quality control methodology: materials, processes, and structural design. Furthermore, in the domain of structural design, they identified a number of challenges related to unknown material properties, calculation input, and design issues, such as reinforcement, joints, and inner pattern design. Besides challenges, DFC brings about new design, dimensioning, and detailing possibilities, which have considerable potential to improve the sustainability of concrete structures, as will be discussed in Section 3. In the following subsections, the structural design and engineering of a number of DFC projects is presented and discussed. Subsequently, the experiences of the engineers in consulting practice will be discussed briefly.

28

29

Table 1: Realised structural DFC projects.

Project name or description	Location, year	DFC fabricator, country	DFC technology	DFC product	Ref.
3D-Printed Concrete Castle	USA, 2014	TotalKustom	Extrusion	Building/house	[62]
Leward Grand Hotel, Hotel Suite	Angeles City Pampanga, The Philippines, 2015	Total Kustom, USA	Extrusion	Building/house	[63]
Office Building	Dubai, May 2016	Winsun, China	Extrusion	Building/office	[63, 64]
Krypton Post	Aix-en-Provence, France, 2016	XtreeE, France	Extrusion	Structural element	[66]
USH Sinusoidal Wall	Paris, France, 2016	XtreeE, France	Extrusion	Building component	[67]
R&Drone Laboratory	Dubai, 2017	CyBe, The Netherlands	Extrusion	Building/house	[68]
Pedestrian Bridge	Madrid, Spain, 2017	Acciona Spain with D-Shape, Italy	particle bed 3d printing	Bridge structure	[69]
Bicycle Bridge	Gemert, The Netherlands, 2017	TU/e, The Netherlands	Extrusion	Bridge structure	[69, 70]
Apis Cor Printed House, Russia	Moscow, Russia, 2017	Apis Cor, Boston, USA	Extrusion	Building/house	[64]
Maison Concept YRYS	Alençon, France, 2017	XtreeE, France	Extrusion	Building/house	[72]
Stormwater Collector	Lille, France, 2017	XtreeE, France	Extrusion	Infrastructure component	[73]
3D Housing 05	Milan, Italy, 2018	Italcementi with CyBe	Extrusion	Building/house	[74]
The BOD	Denmark, 2018	COBOD, Denmark	Extrusion	Building/house	[75]

KnitCandela	Mexico City, Mexico, 2018	NCCR Digital Fabrication, Switzerland	Hybrid techniques	Structural element	[76]
3D-Printed Concrete Pedestrian Bridge	Shanghai, China, 2019	Tsinghua University (School of Architecture)	Extrusion	Bridge structure	[77]
DFAB House	Dübendorf, Switzerland, 2019	NCCR Digital Fabrication, Switzerland	Slipforming, formwork printing, temporary supports, particle bed 3d printing	Building components	[53, 77]
Future Tree	Esslingen, Switzerland, 2019	NCCR Digital Fabrication, Switzerland	Hybrid technique	Structural element	[79]
'De vergaderfabriek', Meeting Room	Teuge, The Netherlands, 2019	Cybe, The Netherlands	Extrusion	Building/office	[80]
Cohesion Pavilion	Innsbruck, Austria, 2019	Incremental3D, Austria	Extrusion	Architectural structure	[81]
Building Apis Cor, Dubai	Dubai, The UAE, 2019	Apis Cor, Boston, USA	Extrusion	Building/office	[82]
3D-Printed Community	Tabasco, Mexico, 2019	ICON, USA	Extrusion	Building/house	[83]
3D-Printed Post-Tensioned Concrete Girder Designed by Topology Optimisation	Ghent, Belgium, 2019	Ghent University (Concre3DLab), Belgium With Vertico, The Netherlands	Formwork printing	Bridge structure	[34]

1

2

3 2.1 Built examples

4

5

6 2.1.1. DFAB HOUSE

7

8

9

10

11

12

13

14

15

16

17

DFAB HOUSE is a collaborative demonstrator of the Swiss National Centre of Competence in Research (NCCR) Digital Fabrication on the NEST building of Empa in Dübendorf, Switzerland. The project involved designing, planning, and building a three-storey house using predominantly digital processes developed within the NCCR Digital Fabrication [84]. DFAB HOUSE opened in 2019 and is used as a residence for long-term research guests. The NCCR Digital Fabrication conducted the architectural design and project management, while Dr Schwartz Consulting was responsible for the structural design with inputs from the researchers of the NCCR Digital Fabrication. Six innovative technologies were used in the fabrication, including spatial timber assemblies [85] and lightweight translucent façades [86], besides the technologies used for the production of concrete structures (see Figure 2) that are presented in the following subsection. The design loads and the structural design followed the SIA 260:2013 [87], SIA 261:2014 [88], and SIA 262:2013 [89] codes, considering a five-year reference lifetime.



Figure 2. Concrete innovations on the first floor of the DFAB HOUSE: *left*, mullions produced with the Smart Dynamic Casting technology; *right*, Mesh Mould double curved wall; *up*, Smart Slab (photo: Roman Keller).

No tests of prototypes were conducted for the DFAB HOUSE, as the structural engineer merely requested material and small-scale structural tests proving that the behaviour was in accordance with conventional structural concrete principles; note that the Swiss structural design codes allow exceptions, provided that they are well founded theoretically or experimentally (SIA 260:2013 [87]). All the structural elements were monitored and inspected periodically, showing no particular issues after one year of use.

Bespoke concrete mullions (Smart Dynamic Casting)

Smart Dynamic Casting (SDC) [37, 89] is an extension of slipforming for producing bespoke concrete structures, which was used in the DFAB HOUSE to fabricate 15 slender reinforced concrete façade mullions (Figure 2, left). The architectural design concept required a variable spacing between the mullions (700 to 1400 mm), leading to different structural requirements for each mullion. Owing to the bespoke fabrication capabilities of SDC, the cross section of each mullion could be reduced to its strict actual needs.

The connections of the mullions to the top and the bottom slabs were designed to avoid the transmission of vertical loads and resist exclusively wind loads. In SDC, concrete manufacturing is continuous, and reinforcement can be easily added before the production (see Figure 3a). Hence, conventional structural design provisions were used to verify the integrity of the mullions and to limit their deflections to 1/400 of their span (because of the requirements of the glass façade). These provisions required the use of $2 \times \text{Ø}12$ longitudinal reinforcing steel bars and $\text{Ø}6$ transversal welded steel bars (see final reinforcement in Figure 3a). In all of the cases, the minimum cross section was set to $70 \text{ mm} \times 100 \text{ mm}$ to ensure the required minimum concrete cover. The widest cross section of the 15 mullions varied from a minimum of $70 \text{ mm} \times 120 \text{ mm}$ to $70 \text{ mm} \times 180 \text{ mm}$ to strictly fulfil the deflection requirement of each mullion. In addition, to ensure the same concrete cover throughout the mullion height and during the slipforming process, the reinforcing bars were precisely pre-bent and clamped before production. In terms of the long-term monitoring of such elements, the only remarkable observations were the shrinkage cracks reported prior to the mullions' installation [37],

1 but they did not compromise the overall structural performance because of the presence of the
2 reinforcement.



5
6 Figure 3. Details of production of concrete structures for the DFAB HOUSE: (a) reinforcement of the mullions installed
7 prior to concrete production [90]; (b) on-site robotic fabrication of double curved reinforcing mesh [42]; (c) 3D-printed
8 formwork for a 7.1-m segment of the Smart Slab [91]; (d) installation of the prefabricated Smart Slab [91].

10 *Mesh Mould double curved wall*

11 Mesh Mould [90, 92] unifies the concrete formwork and the structural reinforcement to avoid the use
12 of conventional formworks. This system was used on the first floor of the DFAB HOUSE to produce
13 a 12-m-long and 120-mm-thick double curved wall (Figure 2, right) that supports the loads of the
14 structural elements above (i.e. Smart Slab and Spatial Timber Assemblies). A double-sided welded
15 steel reinforcement mesh was produced on site by the ‘in-situ fabricator’ robot [93] (Figure 3b) in
16 approximately 19 working days. In the Mesh Mould technology, the dense robotically fabricated
17 mesh is filled with a special concrete mix that achieves sufficient compaction without flowing out the
18 mesh, eliminating the necessity of using formwork. A ready-mix concrete mix (Sika Monotop 412N)
19 was used in the project of the load bearing wall. The concrete cover was sprayed using a ready mortar
20 mix (Sika Monotop 352N). The surface was finished with a customised trowel, containing steel rollers
21 with a radius of 20 mm in order to consistently ensure the required concrete cover thickness.

22 The design value of the vertical loads acting on the Mesh Mould wall was 860 kN, a moderate value
23 for a structural concrete wall. Hence, the system was designed to produce a reinforcement mesh
24 compliant with the provisions of the minimum reinforcement content ($\varnothing 6$ vertical continuous bars
25 and $\varnothing 4.5$ horizontal welded segments, in both cases at an average spacing of 40 mm). The behaviour
26 of the welded segments was studied through both material tests and structural bending tests in
27 elements of a 400-mm span [42]. The bending tests exhibited ductile behaviour prior to the failure of
28 the welding. The observed ductility was caused by the shear deformations induced in the
29 perpendicular continuous reinforcement. While this deviated significantly from the conventional
30 structural concrete, the experimentally proven high deformation capacity allowed the use of a
31 plasticity-based design. The potential formation of weak interfaces between the core and the cover of

1 the wall was studied for different concrete mixes and casting procedures by means of partially loaded
2 area tests.

3 4 ***Smart Slab***


5 The idea behind Smart Slab was to achieve free-form shapes and high-resolution geometric features
6 in concrete structures by using 3D-printed formworks that could be filled and/or sprayed using
7 conventional concrete. In the DFAB HOUSE, the 78-m² Smart Slab is supported by the Mesh Mould
8 wall (see Figure 2 and Figure 3d) and acts as a double cantilever, carrying the two-storey Spatial
9 Timber Units above it. The design concept for Smart Slab was to develop a highly optimised structural
10 component embedding all the details for the façade and technical installations, such as sprinklers and
11 lighting; then, the component was computationally designed to visualise the force flow [91]. The
12 Smart Slab was conceived as a post-tensioned structure, with ribs parallel and perpendicular to the
13 supporting Mesh Mould wall. Each of the 11 prefabricated concrete segments was mounted on site
14 using scaffolding until the activation of the post-tensioning (Figure 3d). The ribs transversal to the
15 Mesh Mould wall carry the main loads, with a maximum cantilever of 4.5 m that required a cross-
16 sectional height between 300 mm and 600 mm. The secondary ribs (parallel to the wall) have a
17 constant depth of 300 mm and carry post-tensioning strands used to compress the joints between the
18 prefabricated segments. With the use of binder jetting sand-printed formworks (Figure 3c), the
19 thickness of the concrete soffits between the ribs was reduced to only 20 mm in thickness. This
20 allowed the reduction of the total weight of the slab to around 15 tons (average concrete thickness of
21 80 mm), corresponding to roughly 35% of a conventional post-tensioned flat slab [91] working over
22 the same spans for the same service loads. The Smart Slab is an example of what can be considered
23 a conventional concrete structure built with a digitally fabricated formwork. Therefore, conventional
24 structural design provisions were used to dimension it, and conventional procedures were followed
25 to install the reinforcement and guarantee its location and cover. Besides the post-tensioning tendons
26 carrying the main forces, the ribs included conventional shear reinforcement.

27 28 ***2.1.2. Future Tree***

29 The Future Tree [94] is a permanent outdoor pavilion (Figure 4a) built in 2019 in a courtyard of the
30 offices of the structural engineering company Basler & Hofmann in Esslingen, Switzerland. The idea
31 of the Future Tree was to develop a project to explore the potential of parametric design and to create
32 an iconic architectural element attracting the attention from inside the building located next to it. The
33 final design included two digital fabrication processes: the Eggshell technology was used to build a
34 structural 2.1-m-tall concrete column, which supported a permeable timber roof of around 100 m².
35 The geometry of the concrete column reflected the timber roof morphology with eight outer ribs
36 serving as a support for the timber profiles (Figure 4).

37 In the Eggshell method, an ultra-thin 3D-printed formwork (Figure 4b, left) is digitally filled with
38 set-on-demand concrete at a speed that is controlled to limit the build-up of hydrostatic pressure to
39 values that the formwork can support [89, 95]. This technology is similar to the smart dynamic casting
40 process, but the use of an ultra-thin formwork allows for more complex geometries. In the Future
41 Tree, the formwork was just 1.5-mm thick and made from a polymer that could be recycled after the
42 column was built. The researchers of the NCCR Digital Fabrication carried out the architectural
43 design and digital fabrication of the column, while Basler & Hofmann was in charge of the structural
44 analysis. Eggshell allows the digital fabrication of complex column structures in a continuous casting
45 process with similar mechanical performances as conventionally built structures. Hence, in these

1 applications where a reinforcing bar cage can be fit to the formwork geometry (as for the Future Tree
2 column, see Figure 4a, centre), the structural design can be addressed by essentially conventional
3 procedures. In this particular application, the design loads and the structural design followed the SIA
4 261:2014 and SIA 262:2013 codes [87, 88].
5



6
7 Figure 4. Future Tree pavilion in Esslingen, Zurich: (a) completed pavilion (Image: Basler & Hofmann AG, Stefan
8 Kubli); (b) Eggshell column, from left to right, printed ultrathin formwork, reinforcement cage, and finished concrete
9 element (Image: Gramazio Kohler Research, Joris Burger).
10

11 The core of the column was dimensioned to resist the global loads of the timber roof, which required
12 eight $\text{\O}14$ longitudinal bars and $\text{\O}10$ stirrups at a spacing of 150 mm. The eight ribs were reinforced
13 to contain the minimum reinforcement to guarantee the crack width control and to avoid brittle
14 failures at cracking (i.e. a reinforcement ratio of more than 0.6% for the longitudinal reinforcement
15 and more than 0.1% for the shear reinforcement). The minimum reinforcement of the whole rib was
16 calculated for its largest section ($200 \text{ mm} \times 70 \text{ mm}$), resulting in $\text{\O}14$ longitudinal bars at the edge of
17 the ribs and transversal $\text{\O}10$ bars at a spacing of 80 mm. The structural engineer did not require the
18 tests of prototypes, as the dimensioning was possible by following essentially conventional methods.

19 **2.1.3. KnitCandela**

20 KnitCandela (Figure 5) is a thin, undulating, 50-m^2 concrete shell built in 2018 at the *Museo*
21 *Universitario Arte Contemporáneo* (MUAC) in Mexico City. The shell was designed in collaboration
22 between Zaha Hadid Architects and the researchers of the NCCR Digital Fabrication as a homage to
23 the Spanish–Mexican shell builder Félix Candela. The concept was to explore how the range of
24 buildable concrete shell geometries can be expanded by the use of novel computational design
25 methods and a custom-knit textile as a lightweight stay-in-place formwork that allows the generation
26 of a ribbed structure. In KnitCrete, the formwork is coated with a thin layer of fast-setting cement
27 paste [96] that serves as a first stiffening layer for the textile, minimising formwork deformations
28 during the application of further concrete layers.
29



Figure 5. Finished KnitCandela concrete shell showing the soft textile interior and the smooth concrete exterior [96].

KnitCandela was located inside a museum and classified as an artwork. Hence, the conducted structural verifications [96] (limitation of concrete stresses and deflections) had to prove the safety of the shell but without having to strictly follow any particular building code. The shell was considered unreinforced for these verifications (the contribution of the textile was neglected), but a small amount of glass fibres was added to the concrete mix provided by Holcim Mexico in order to ensure crack distribution and predefined capacity redistribution.

2.1.4. Bicycle bridge Gemert

In 2017, at the initiative of contractor BAM, a bicycle bridge mainly consisting of six extrusion-based 3D concrete printed parts was realised in Gemert, the Netherlands (Figure 6). The project is extensively described by Salet *et al.* [42, 97]. Structural engineering was performed by Witteveen+Bos consulting engineers, in close collaboration with Eindhoven University of Technology (TU/e), which also provided all the experimental testing. The parts were printed at the TU/e 3DCP facility and moved to the site, where they were joined to the bridge element.



Figure 6: 3DCP bicycle bridge in Gemert, at the opening event in October 2017 (photo: Kuppens Fotografie)

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21

As the bridge would be the first of its kind, a conservative fail-safe concept was adopted. It featured parts that would be rotated 90° after printing and stacked together by full pre-stressing.

The design of the single segments was purposefully kept relatively simple, bearing the characteristics of the 3DCP facility in mind. The segments had two straight sides, acting as the top and the bottom of the bridge. In between, a ‘bottle-shaped’ pattern of the filament was designed to transfer shear forces (Figure 7). The density of the infill pattern and the outer dimensions (to some extent) were at the discretion of the structural engineer as a function of the structural requirements. In contrast to the default 40-mm width of the facility, a 60-mm filament width was applied to increase robustness.

To avoid any unforeseen structural behaviour, a full 3D non-linear finite element model (FEM) was developed for the structural calculations. The design loads were taken from EN 1991 [98,99], while the input material properties and checking criteria were obtained from experimental testing at the TU/e, from which design values were derived according to EN 1990, Annex D [100]. This provided directionally dependent compressive and tensile strength data, as well as the data on stiffness, shrinkage, and creep. However, despite a rather extensive experimental campaign, note that because of the large number of parameters to be tested, the average sample size is still limited and not all of the process variables could be taken into account. Moreover, the applied experimental methodologies were in the early stages of development and are still evolving.



Figure 7: Printing of one of the parts of the bicycle bridge at the 3DCP facility of the TU/e

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33

In the direction of the main span, the pre-stressing action was applied by post-tensioned rods, anchored in cast concrete head blocks and fed through openings in the segment structure, which serve as active reinforcement (as clearly visible in the mock-up structure of Figure 16, which is discussed in Section 4.1); this concept did not disrupt the printing process. In the perpendicular direction, an innovative concept of the entrained high-strength steel cable reinforcement was applied over a part of the height [101, 102] as an experimental addition. These cables were intended as compatibility torsion reinforcement in case of misalignment in the abutments (hence, they provide an additional precaution, but the structural safety of the bridge does not rely on them). As the cables were galvanised, the considerations of the concrete cover were omitted.

The building permit was obtained from the local authorities on the basis of the ‘Design by Testing’ approach provided by Annex D of the EN 1990. In addition to the material tests, two large-scale tests were performed. First, a destructive four-point bending test on a 1:2 scale mock-up of the bridge was performed to verify the failure resistance and the failure behaviour. Subsequently, an on-site loading test to the serviceability limit state was performed on the actual bridge. Considering the design concept in relation to the results of the experimental results on different scales, the bridge was considered safe for use.

Important lessons were learned from this first bridge. According to the design, the anchor blocks should have been supported continuously on two foundation beams supported by piles. However, these beams and the bridge were not fully aligned, resulting in a torsion moment in the post-tensioned but unreinforced printed segments. This was suspected to be the cause of some of the cracks that appeared after installation. Besides, the impact of shrinkage differences caused by both drying shrinkage and temperature gradients induced longitudinal cracks in the printed segments over time. Neither crack was critical, but they were a consequence of the slender dimensions of the printed filaments compared to the massive traditional structures (which is a serious issue to consider).

2.1.5. Cohesion pavilion Innsbruck

The Cohesion pavilion was designed, fabricated, and constructed on a publicly accessible square in Innsbruck, Austria, in 2019, over a period of just 11 weeks (Figure 8). It celebrates the 350th anniversary of the University of Innsbruck. The architectural and structural design was developed by a small team of students and staff of the University of Innsbruck in collaboration with Eindhoven

1 University of Technology. The complex free-form pavilion, characterised by a multitude of
2 developing and merging double curved surfaces, consists of 47 radially positioned, unique parts. The
3 outer surface of each part was dictated by the architectural design, while the infill was to be designed
4 according to the structural needs. The parts were produced by Incremental3D using extrusion-based
5 3D concrete printing, with the two-stage material supplied by Baunit. The on-site construction was
6 performed by contractor PORR. A detailed description of the project was provided by Grasser *et al.*
7 [81].
8



9
10 Figure 8: Cohesion pavilion, celebrating the 350th anniversary of the University of Innsbruck (Photo: Rupert Asanger).
11

12 Considering the short time span available, a robust and efficient approach was selected. First, the
13 structural principles were determined. Each part was designed to be self-supporting. To avoid
14 extensive reinforcement, the parts were dimensioned not to exceed the concrete tensile strength, with
15 the exception of the heavily cantilevering ‘table’ (see Figure 8). Reinforcement was only applied to
16 ensure structural safety, not to act in tension under the in-service conditions.

17 To determine the design loads, the pavilion was considered a Consequence Class 1 (CC1), Reliability
18 Class 1 (RC1)-type structure as defined by the EN 1990-1, with a five-year reference lifetime.
19 Determining the location and magnitude of loads that should be considered to act on the structure was
20 difficult because of the irregular geometry. Conservative assumptions had to be made. The distributed
21 and concentrated vertical loads were considered feasible on any part of the structure with a slope of
22 45° or less with the horizontal. However, the concentrated horizontal-line loads were governing in
23 the more critical parts.

24 Each part was individually designed and analysed. A simple linear elastic 2D FEM approach in one
25 or more radial planes of the part was adopted. For the larger parts, a model with linear geometries
26 was initially used to gain insight into the order of the magnitude of stresses and develop a principal
27 design of the infill pattern, which was followed by a surface geometry-based analysis to check and
28 verify. The maximum principal tensile stress was taken as the checking criterion.

29 The material supplier provided data on the bending and compressive strength of the material, as well
30 as the Young’s modulus value and an estimate of shrinkage. However, because of a lack of
31 standardised testing methods, these had to be treated as global indicators because details such as

1 sample size, testing direction, and printing conditions were unreported. Globally, a material safety
2 factor of $\gamma_M = 2.0$ was applied to account for the limited experimental data available. Additional safety
3 was to be provided by the reinforcement.

4 The structural geometry design was based on the assumption that any geometrical width should be a
5 multitude of the print filament width of 30 mm. The internal structures were mostly designed in an
6 orthogonal manner (vertical and horizontal), as this was expected to be the easiest way to control
7 shrinkage cracks in printing, leading to parts that would be less susceptible to shrinkage stresses than
8 parts with diagonal infills. Figure 9 shows the pavilion during construction, with some insides of the
9 parts on display.

10



11

12

13

14

Figure 9: Details of Cohesion pavilion, celebrating the 350th anniversary of the University of Innsbruck (Photo: Freek Bos)

15

16

17

18

19

20

21

22

23

24

25

26

27

28

29

30

In general, reinforcement in the form of either woven carbon fibre-reinforced polymer, CFRP, or steel bars was applied twice in each printed part, between layers at approximately 1/5th and 3/5th of the part height and calculated to be sufficient to carry the ultimate limit state tensile loads in the corresponding section. Considering the short reference life span, the nominal concrete cover of 27 mm on most steel bars was considered sufficient. In some cases, the reinforcement was embedded in only one filament. This reduced the cover to 12 mm, but in these areas, the reinforcement was heavily over-dimensioned and therefore accepted. Because of the size and location of the pavilion on the university grounds, no separate approval for the structural design was required by the authorities. All of the CFRP elements formed continuous (semi-rectangular) geometries so that their reinforcing performance would not depend on the bond with the concrete, as this was expected to be limited because of the strand smoothness. Because of the time constraints, these innovative CFRP reinforcements were only applied to a selection of the higher parts in the outer ring, while conventional reinforcement bars with a diameter of 6 mm were manually applied to reinforce critical sections of the remaining parts. As advanced bar bending equipment was unavailable at the manufacturer, only straight bars or bars with one 90° angle were used. In several cases, the infill pattern was particularly designed to allow the embedment of such bars.

1 During construction, one part was severely damaged by collision from a fork-lift truck, to which these
2 parts are more sensitive than conventional concrete parts because of their filigree nature. In the
3 months after construction, several shrinkage cracks have been reported in the parts. A comprehensive
4 evaluation of the state of the structure is planned for a later date. Printing mortars generally exhibit a
5 high level of shrinkage, but in this project, the speedy fabrication process, which in some cases saw
6 parts being implemented on-site in a week after printing, may have been aggravated by the lack of
7 controlled curing conditions.


8 ***2.1.6. 3D-printed concrete girder designed by topology optimisation***

9 The lab-scale footbridge project shown in Figure 10 and Figure 11 and thoroughly discussed in [34]
10 is a post-tensioned DFC girder (4-m span) that was constructed at Ghent University in 2019. The 2D
11 shape of this girder was optimised using topology optimisation techniques developed at Technion-
12 Israel Institute of Technology. With advanced algorithms, not only the concrete distribution was
13 optimised, but the optimal shape and curvature of the post-tension cable were also determined. The
14 objective was to minimise the displacements at the top surface of the beam, because of the combined
15 action of the external loads and the post-tensioning tendon [103]. As the implementation of the
16 optimisation procedure was until then developed in 2D, some post-processing was necessary for the
17 final design, and a 3D finite element analysis was performed to determine the design values and
18 limits. Similar to the bridge project in Gemert, the final structure was made from multiple concrete
19 segments that were printed independently and then compressed together with the tendons. However,
20 in this project, the internal cavity was grouted to create a solid shape. As such, and in contrast to the
21 other projects, the digitally fabricated system can be classified as a formwork printing process.


22 With regard to the 3D finite element analysis, note that the FE model of the girder did not include the
23 complex interaction between the 3D-printed formwork and the solid infill. Instead, a homogenised
24 Young's modulus value and the associated concrete grade (C30/37) were used in the simulation. The
25 production of the 3D-printed segments was realised in collaboration with Vertico, and the printing
26 setup was made of the following: (i) a six-axis ABB robot arm, (ii) a mortar (screw) pump with a
27 delivery rate between 2 and 29 L/min, and (iii) an open-source concrete printing mixture. The
28 assembly, integration of reinforcements, and grouting process were performed at Magnel Laboratory
29 for concrete research. There, the produced segments were positioned with their large side flat on the
30 floor, rebars ($\text{\O}12$ mm) were inserted, and the segments were slightly pre-stressed up to 5 kN. Next,
31 the joints were sealed with a foam gun to close the remaining gaps, and four 30-mm holes were drilled
32 to fill the internal cavity with grout. The same pumping system, as that used for the 3D concrete
33 printing, was used to pour the grout. This grout material was a high-quality shrinkage-compensating
34 high-strength seal mortar with a compressive strength of ~ 60 MPa and a tensile strength of ~ 12 MPa.
35 After a hardening period of 14 days, the girder was lifted from the ground and the full post-tension
36 force of 50 kN was applied to the lower tendon (type: 3/8"; presented in 'cyan' in Figure 10**Errore.**
37 **L'origine riferimento non è stata trovata.**). With respect to the reinforcement cover, the tendons
38 were enclosed by the post-tensioning duct and kept in the middle of the concrete volume by plastic
39 point spacers. The steel rebars in the struts were connected to the tendons and run through the mid-
40 section.

41 Finally, the girder structural performance was experimentally verified using digital image correlation,
42 and its deflection was compared to the numerical results. The upper chord showed an excellent fit
43 between the experimental and the numerical results. No destructive testing has thus far been

1 performed on this case study. In the referenced paper, a comparison was also made to a T-section
2 girder with the same total deflection, presenting material savings of roughly 20%.



3
4 *Figure 10:* Results of (a) the topology optimisation procedure, for a single-span beam subjected to a uniform load and
5 (b) the dimensioning procedure, showing the 12-mm rebars in the struts and 9.4-mm tendons in the top and the bottom
6 chords [34].
7



8 *Figure 11:* Completed optimised girder - Source: (a) Vertico 3D concrete printing and (b) the individual DFC elements
9 before assembly [34].
10
11

12 **2.2 Structural engineers' perspective**

13 The issues associated with the structural engineering of DFC projects were further confirmed by
14 structural engineers operating in practice. The authors spoke to Hans Laagland of Witteveen+Bos
15 Consulting Engineers. At the time of writing, Laagland had been closely involved in three completed
16 projects and was working on at least three other projects under construction in Dubai and the
17 Netherlands, all of which were bridges or small buildings with extrusion-based 3D-printed concrete
18 (3DCP) structural elements and with building permits for general use. This subsection discusses his
19 experiences.

20 In conventional structural concrete projects, seasoned engineers have developed extensive knowledge
21 and confidence from personal experience, codes, and guidelines. For a variety of reasons, this is
22 entirely lacking in 3DCP, resulting in questions such as 'what is the variation in material quality?',
23 'what are the dimensional variations that occur?', 'how well are the layers stacked on top of each
24 other?', and 'how well founded are the given properties from a statistical point of view?'.

25
26 To deal with this, an approach that significantly deviates from the conventional way of working is
27 needed. First of all, it should require the structural engineer to be explicitly involved in many aspects
28 of the project, most of which are normally regulated by codes and therefore do not need further
29 explicit involvement. This includes material production, determination of structurally relevant
30 properties, print production process control, logistics, and on-site construction. Furthermore, it
31 requires careful consideration in structural modelling, with customised material properties. For
32 instance, the density may have to be increased artificially to account for the possible increases in
33 filament width, without simultaneously influencing sectional stiffness as the filament width may also

1 be nominal or less instead of more. In addition, a risk inventory ('what if...') is an appropriate
2 instrument to reduce the failure probability.

3
4 In conventional concrete construction, the dimensioning and checking rules based on mechanical
5 static analyses are supplemented by detailing rules based on experience to account for the unexpected
6 deviations from the actual structure to the modelled one, as well as for effects that are not explicitly
7 covered in these analyses. As such experience-based rules are unavailable for 3DCP, significantly
8 more explicit consideration and testing of the possible failure mechanisms and quality control is
9 required.

10
11 Another important effect of the introduction of 3DCP is that the nature of concrete structural elements
12 in terms of mechanical response deviations from those of conventional concrete. Local stability and
13 strength effects such as local and plate buckling have become highly relevant and possibly governing.
14 Because of the filigree nature of 3DCP structures, the thermal storage capacity is considerably less,
15 which may result in cracking due to thermal expansion. To identify all of these possible failure
16 mechanisms, Witteveen+Bos performs extensive 3D non-linear finite element analyses (FEA) on its
17 3DCP projects, for both mechanical and thermal loads.

18
19 Structural engineering with DFC is further complicated by the fact that there are no material
20 classification standards. The few commercially available printable mortars vary widely in
21 composition and properties as well as price. Often, element manufacturers only work with one
22 material supplier. Structural property data are often not easily shared by material suppliers because
23 of the competition in material development. This makes an economical, fit-for-purpose selection of
24 material and structural design very difficult. Furthermore, the lack of certified ancillary products,
25 such as anchors, is a practical but significant obstacle in the general structural use of DFC.
26 Nevertheless, the experience of Witteveen+Bos in acquiring building permits for DFC structures is
27 fairly positive. In Europe, Annexure D of the EN 1990 provides a global basis to approve structures
28 that fall outside the scope of the other parts of the Eurocode. It has turned out to be workable in
29 practice. When given the appropriate attention, e.g. by showing production facilities, the authorities
30 in both Dubai and the Netherlands have shown willingness to give this new technology the required
31 reasonable amount of testing to prove its structural safety. The testing sequence, generally, consists
32 of four steps. Material tests are initially needed to determine the properties required for the structural
33 analysis. Subsequently, a (destructive) mock-up test is required to examine the validity of the design,
34 and no unexpected failure mechanisms occur. When this is confirmed, the design can be constructed
35 and tested in-situ to ensure that the actual construction has been produced according to the design.
36 Finally, a checking or control procedure during the life span of the structure should be enacted to
37 identify the possible unknown long-term effects.

38
39 Currently, in DFC projects based on structural concepts similar to those developed earlier,
40 Witteveen+Bos is moving from the full-scale testing of the overall structures to a more detailed testing
41 of local effects. Moreover, the gradual increase in experience allows a step-by-step reduction of the
42 excessive safety measures toward more optimised topologies. Finally, it should be recognised that
43 the application of such innovations requires openness that can only be achieved in combination with
44 real teamwork.

3. OPPORTUNITIES

3.1. Specialised computational methods

Terms such as ‘design complexity’ and ‘freeform architecture’ are often cited as the primary advantage of DFC. Nevertheless, its true implications for creating optimal, sustainable, and weight-efficient constructions are largely underexploited. More often, design complexity is enforced by designers and architects for aesthetic reasons only, while the structural design opportunities envisioned by digital fabrication are somewhat being neglected. This is mainly attributed to the fact that appropriate tools to fully exploit them, also in terms of a commonly agreed ‘tailored’ design and code-regulation framework, may not yet be fully available.

Many recent projects mention structural optimisation theories, often referring to topology optimisation and generative design, in an attempt to optimise the structural efficiency. Topology optimisation (TO) is a mathematical method that is generally used to optimise the material layout within a design space for a specific set of loads and design constraints. Using this technique, engineers can impose limits so that a design uses the resources optimally while remaining physically viable. As the results from such an optimisation are often very complex in shape, their coupling with DFC (or additive manufacturing, in general) is natural. The most common TO approach is the minimum compliance design problem, which minimises the strain energy of a structure (equivalent to maximising its stiffness), as depicted in Figure 12. Currently, engineers mostly use this method in their structural designs because the mathematical implementation is straightforward and computationally very efficient. For each iteration in the optimisation process, only one finite element analysis needs to be performed to gather all the necessary sensitivity information. However, when linking TO to the design of concrete structures, the use of a conventional compliance-based method is rather limited, because it fails to incorporate the non-linear behaviour of the material (i.e. concrete having different strengths in traction and compression). In response, several extensions to the original formulation have been proposed thus far [104–107] and for the simultaneous optimisation of concrete and rebars [108–110].




Figure 12: Result of a topology optimisation study of a rectangular design domain subjected to a concentrated load [15].

However, only few of these algorithms have found their way into mainstream use; the common methodology involves using minimum compliance designs in the conceptual design stage; thereafter, several more design iterations are performed using traditional finite element modelling for studying the buckling behaviour of local members, fatigue constraints, vibrations, fire safety, robustness, etc.

1 Additionally, in order to not restrict the practical cases to formulations specifically made for the
2 design of concrete structures, recent approaches have also been developed for linking TO to additive
3 manufacturing in general, e.g. overhang limitation for TO [111, 112], minimisation of support
4 structures [113], and optimisation with anisotropic materials and infills [107, 114, 115]. Moreover,
5 several multi-disciplinary aspects could be included in the optimisation process as well, e.g. the
6 optimisations of the thermal resistance of wall structures, fire safety, and acoustics are all very
7 important and often make use of multi-material optimisation techniques where the positioning of the
8 materials is crucial; in this latter case, a link can also be made to multi-material 3D printing [116,
9 117].

10 Finally, because of the novelty of 3D concrete printing techniques, the process-specific limitations
11 and constraints imposed by the manufacturing process are still mainly unclear. Designs that are
12 optimised according to specific TO algorithms (in their current implementation) may behave
13 unexpectedly or even suffer from damage because of the unforeseen consequences of the digital
14 fabrication process. The application of TO algorithms that incorporate the anisotropic material
15 properties of digitally fabricated concrete will be required, but currently, TO awaits fundamental
16 investigation about time, location, and fabrication path-dependent material characteristics. Moreover,
17 advanced properties such as layer cohesion, layer interaction, release of hydration energy, thermal
18 strains, and relaxation shrinkage will be important as well. With the final aim of providing better
19 input for the TO algorithms, the first structural design opportunity therefore lies in the investigation
20 of these advanced physical–mechanical characteristics.


21 Furthermore, an additional opportunity is not focused on optimising the design in the hardened
22 material state, but rather on optimising (or simulating) the finalised design for the manufacturing
23 phase. The reason for this is that many optimised designs are just ‘not ready’ to be digitally fabricated
24 with the current technology capabilities. In other words, models (both analytical and numerical) that
25 can determine and predict how a DFC element behaves while the concrete is still fresh following a
26 topology-optimised fabrication path, are currently desired. Firstly, such models can offer direct
27 improvements in reducing costs and labour-intensive printing experiments, and limit the number of
28 failed printing attempts. Secondly, these models can offer the potential to further tune the existing
29 structural optimisation strategies and help to solve key challenges in the future.

30 To this end, different analytical models already exist and have been developed for concrete printing
31 applications (mainly layered extrusion DFC processes). For example, Suiker [118] proposed a
32 mechanistic model to analyse and optimise the mechanical performance of straight unreinforced wall
33 structures in 3D printing processes. The model investigates the influence of the printing speed, curing
34 of the material, and geometrical features on failure mechanisms such as elastic buckling and plastic
35 collapse. In contrast, Roussel [50] presented a set of analytical equations studying the rheological
36 requirements for the printable concrete structures needed to control the final geometrical dimensions
37 of a structure. Among others, the layer interface strength, strength-based stability of the first layer,
38 and overall buckling stability of the total structure are discussed. Both methods demonstrate good
39 agreement with the experimental results. However, they can only be used in the case of simple
40 rectangular structures or structures with straight cross sections, as the application of these equations
41 is not valid for all (free-form) shapes. In response, Wolfs *et al.* [52, 119, 120] first proposed a
42 numerical model using 3D finite element analysis to investigate the fresh early-age mechanical
43 behaviour of 3D-printed structures. The model uses the implicit solver within Abaqus to simulate the

1 continuous extrusion of concrete layers on top of each other, until failure. While requiring a
2 significantly higher computation time, the model provides interesting new insights into the print
3 process, paving the way to simulate complex geometries. A different approach is taken by Kruger
4 [121] and Reinold [122], where the rheological material properties form the basis for the prediction
5 analysis. Reinold [122] developed a numerical model based on the particle finite element method that
6 can assist with the understanding of the complex interaction between the printing process and the
7 evolution of structural parameters throughout the manufacturing process.

8 The potential for all of these simulation techniques is to provide quick preliminary data and enable
9 improved production processes for DFC. Basic implementations can help construct design rules and
10 link digital design information with the physical production processes (e.g. as in the process shown
11 in Figure 13). Secondly, a coupling between the existing topology optimisation algorithms can be
12 made and foster reliable design opportunities.

13



14 Figure 13: Complete digital design-to-manufacture process of a segment of the optimised design presented in [34]: (a)
15 3D poly-surface (b) slicing and tool-path generation, (c) process simulation, and (d) actual fabrication

16

17 Note that the simulation techniques described above focus primarily on the fabrication process. To
18 date, much less work has been carried out on the structural design of the final product of the
19 fabrication process. Here, these methods need to combine the intrinsic properties of 3D printed
20 concrete with the structural integrity requirements and the related mechanical models for
21 conventional reinforced concrete structures. Therefore, it is possible to find new structural design
22 concepts, such as weak interface design, which will be discussed in the next section.

23


24 3.2 Structural design concepts

25 Over the past few years, the digital fabrication research community has developed diverse digital
26 fabrication technologies. The researchers have placed a strong emphasis on material and geometrical
27 aspects, whereby the structural aspects have been typically regarded only as challenges. For example,
28 the difficulty to integrate reinforcement during the manufacturing process or the negative impact of
29 weak interfaces on the mechanical behaviour has been extensively discussed but not solved. Further,
30 note that digital fabrication offers many new opportunities to the conceptual design, dimensioning,
31 detailing, and production of concrete structures. Some opportunities related to structural design
32 aspects are discussed in this section. The potential of geometric flexibility is the only one that has
33 already been extensively explored. With digital fabrication, concrete can be placed selectively where
34 needed, and complex geometries may be produced without additional effort. This is certainly a major
35 advantage, which opens the way for using structurally optimised shapes (reducing material

1 consumption). However, this advantage is limited in many cases, particularly in buildings, because
2 of the existence of the requirements for geometric simplicity that are independent of the construction
3 technology [123]. Despite the fact that geometric flexibility has already been explored, most of the
4 promising processes are currently competitive only for special applications. Therefore, further
5 opportunities for more efficient structural design should be explored in order to be able to exploit the
6 full potential offered by DFC in geometrically simple structures and to solve the current issues of
7 high costs and lack of compliance with structural integrity requirements. One possibility to comply
8 with the requirements of geometric simplicity while taking advantage of the geometric freedom and
9 the possibilities of multi-material printing is the use of complex cross sections, in which the materials
10 are selectively placed to optimally fulfil several functions (e.g. insulation).

11 Mata-Falcón *et al.* [48] formulated additional opportunities related to the saving of structural
12 reinforcing steel. For example, reinforcement quantities required for the ultimate limit state can be
13 significantly reduced by using a robotic placement of the reinforcement [93], which allows the
14 provision of reinforcement in the optimum directions and strictly in the statically required amount.
15 This might be particularly interesting for walls and slabs. Another promising opportunity is the
16 reduction of the minimum reinforcement, which often makes up for more than 50% of the total
17 reinforcement content [48]. The minimum amount of reinforcement is always required in concrete
18 structures to avoid brittle failures at cracking and increases proportionally to the cracking load of the
19 structures. Therefore, measures aimed at reducing/controlling the cracking load may reduce the
20 minimum reinforcement very significantly. One possibility in this direction is to tailor the concrete
21 grade locally to the actual needs (e.g. reducing the cement content where a low concrete strength is
22 sufficient) [48]. While the current DFC processes do not allow for this, it is likely that this will be
23 possible in the future, given the great potential to decrease both the use of cement and the amount of
24 reinforcement required. Besides reducing the tensile strength of concrete everywhere, a further option
25 to reduce the cracking load and to ensure appropriate serviceability behaviour is to produce weak
26 sections in the structure. This corresponds to the concept of crack initiators that digital fabrication
27 technologies can introduce by means of geometric or material discontinuities [48]. One example of
28 intrinsic crack initiators caused by material discontinuities is the weak interface between concrete
29 layers generated in many additive manufacturing processes (e.g. 3D concrete printing). A simple
30 mechanical model [48] shows that a reduction in the tensile strength at the weak interface allows the
31 proportional reductions of the cracking load, crack spacing, and crack widths for a given applied load.
32 The results of this model agree with the experimental observations of crack widths shown in Figure
33 14 [125]: for the same load, the layered specimen with the reduced tensile strength (by 30%) leads to
34 average crack widths of around 30%–40% lower than in the reference specimen without layers. In
35 this sense, the reduction of crack widths introduced by a weak interface can be used in elements where
36 the serviceability design is critical to reduce the content of the minimum reinforcement and/or
37 improve the durability. In spite of these advances, most of the discussed opportunities for improving
38 the efficiency of structural designs remain unexplored today. Moreover, there will still be a plenty of
39 unforeseen opportunities. One of these could be the development of more structurally efficient or
40 more environmentally friendly reinforcing strategies, which would be possible only because of digital
41 fabrication processes. Therefore, it is likely that an effort in this field of DFC will contribute to finding
42 the key for producing more sustainable and economical concrete structures.

43



1

2

3

4

5

6

4. STANDARDS AND GUIDELINES FOR DFC STRUCTURES: ON-GOING INITIATIVES

7

8

9

10

11

12

13

14

15

16

In the highly stimulating and dynamic framework of increasing DFC applications with a large variety of cement-based materials, clearly led by the industry, the research community has felt the need to flank and support such a challenging activity of setting up adequate transnational initiatives. The latter aim to point out, first of all, the material science and engineering fundamentals underlying the concept, design, and production of ‘digitally manufacturable’ and ‘digitally manufactured’ cement-based materials. Such a task is also instrumental in highlighting the research needs and fostering the development and technology transfer in a coordinated manner, along with paving the way toward the development of material and product standards as well as established design approaches. The final goal is to achieve consistency and harmonisation with the approaches currently governing the design of conventionally cast reinforced concrete structures.

17

18

19

20

21

22

23

24

As a matter of fact, RILEM launched in May 2016 at the 8th International RILEM Symposium on Self-Compacting Concrete held in Washington, DC, USA, the first transnationally initiative on digitally fabricated concrete through the namesake *Technical Committee 276-DFC Digital Fabrication with Cement Based Materials*. The Committee, having regularly convened at least thrice a year, not only has started to organise a successful series of International Conferences, now in its second edition, but is also en route to releasing the first international state-of-the-art report on the topic. The report, moving from the materials science fundamentals governing the concept and explaining the processing properties and signature performance of digitally fabricated materials and

1 structures, provides a framework to rationally tackle the conceptual and structural design of the
2 engineering applications.

3 This challenging task, like a gauntlet thrown by the RILEM RC, has been undertaken by the recently
4 constituted *fib Task Group 2.11 Structures made by digital fabrication*, which held its kick-off
5 meeting in Krakow in May 2019. The goal of the Task Group will be the development of specific
6 testing and design guidelines in the growing area of digital fabrication with concrete, by defining the
7 preliminary structural code prescriptions, e.g. in the form of annexes to the current codes, such as *fib*
8 *Model Code 2010*, valid for conventionally cast reinforced concrete structures, as well as by
9 complying with the recently reapproved ISO - ISO 22966:2009 - Execution of concrete structures
10 [125].

11 In the same framework, and fruitfully exploiting its signature healthy interaction between the
12 academia and the industry, as well as the synergy with the existing technical committees dealing with
13 the related specialty topics, from materials science to workability to fibre-reinforced concrete, ACI
14 has also recently formed *ACI Committee 564: 3D printing with cementitious materials*. The
15 Committee held its first meeting during the 2018 fall convention and has undertaken the task of
16 writing a state-of-the-art report in a form consistent with the ACI document library. Moreover, it has
17 also been regularly organising dissemination and educational events on topics related to 3D printing,
18 which have been instrumental in marking the most recent global milestone developments as well as
19 addressing cutting-edge topics, such as the integration of reinforcement in 3D-printed/digitally
20 manufactured concrete structures.


21 Multi-fold involvement in either of the aforementioned initiatives of scholars and industry leaders is
22 a guarantee of synergic cultural cross-fertilisation in fostering the development of a topic that is likely
23 to stand as a breakthrough milestone in revolutionising the innovation uptake of the concrete
24 construction industry.

25 **4.1 Example of DFC structural design protocol**

26 An example of the need for providing an internationally harmonised structural design and material
27 acceptance framework for DFC structures (or even a pathway which has to be followed for
28 implementing such a task) is represented by the case study of the 3DCP bicycle bridge in Gemert,
29 The Netherlands. In detail, it is well accepted that the current public system of regulations governing
30 structural design and construction aims to guarantee the essential performance requirements to protect
31 the citizen. With a focus on Europe, this means that the safety in the construction industry needs to
32 be ensured at three different stages: building preparation or design (EN-1992-1-1 [126]), building
33 construction (EN 13670 [127]), and materials supply (EN 206 [128]). Unfortunately, the pre-stressed
34 bridges at issue do not comply with any of these regulations. In terms of design, the minimum amount
35 of reinforcement is lacking, particularly in the cross section. Moreover, the flow of forces is
36 considerably more constrained in the printed segments by the tool-path, leaving less room for the
37 redistribution of forces in combination with the plastic deformations of the reinforcing steel.
38 Furthermore, the material properties of printed concrete are not known from the regulations and
39 cannot be tested accordingly to them; this is attributed to the fact that testing cannot be done using
40 standard cylinders without applying intense vibrations. Besides, the impact of the typical layered
41 structures most likely needs to be tested as well, taking into account the printer settings and ambient
42 conditions. One can even question whether the mortars that are printed, without coarse aggregates,

1 can be considered concrete, indeed. Finally, the construction is fundamentally different in terms of
2 printing, but the construction of the segments into a bridge contrary is rather traditional and well
3 regulated.

4 Fortunately, the regulations anticipated such a situation. Annex D of EN-1990 [100] describes a
5 procedure for supporting the design by testing. A special protocol has been developed to embed the
6 idea in the design and realisation of the post-tension bridges, as shown schematically in Figure 15.



7
8
9

Figure 15: Protocol followed in the design of the post-tensioned bridges

10 The protocol starts by defining the ultimate limit state and approaches the design of the bridge,
11 accordingly, using standard tools and the available design code. The material properties of the printed
12 concrete still have to be assumed at this stage on the basis of the data collected from previous tests.
13 Thereafter, a mock-up is made and structurally tested up to failure, and its structural behaviour
14 compared to the design predictions (Figure 16).



15
16
17

Figure 16: Large-scale testing, as part of the protocol at TU/e

1 The predictions must be updated prior to the comparison with the material properties tested on the
2 actual mock-up. The additional materials tests provide the designer with the required stochastic data
3 that are collected in line with the rules defined in Annex D of EN-1990. Note that the designer in-
4 charge also needs to define the type of structural behaviour that needs to be compared between the
5 design and the tests upfront and thus, the need for appropriate measuring devices.

6 In case of an unexpected behaviour, a re-design may be needed. If the behaviour in the test matches
7 with the design, the production can start. However, in the case study at issue, the bridge will be tested
8 on-site again in terms of its structural integrity before being used. The reason for the additional tests
9 is the difference in the manufacturer and the manufacturing circumstances between the mock-up and
10 the full bridge and the simple fact that the real bridge is considerably larger than the part tested in the
11 mock-up; this leaves higher chances for imperfections. Obviously, the on-site testing of the bridge is
12 not conducted up to failure. Instead, a type of diagnostic test is performed, which can also be coupled
13 with continuous monitoring to check for deviations, if any, from the predictions along the time,
14 because of different causes, including material and structure aging, accidental events, change in loads,
15 and environmental actions. The load test should be sufficiently high to measure any structural
16 response, but not so high as to avoid unnecessary damage. This trigger limit is defined on the basis
17 of the mock-up definition. Finally, the material properties of the bridge are again tested as a measure
18 of quality control.

19 It is realised that the protocol is rather robust, particularly if the bridge is loaded in the diagnostic test
20 up to the ultimate design load again. However, the idea is to consider the bridge as a mass-customised
21 type of product that will be produced in series over time. The ones tested with a mock-up most likely
22 are just the first out of a large series. Once the confidence has been gained that the structural behaviour
23 can be well predicted with design tools, attention may then focus on the single components of the
24 bridge, such as shear strength (including the size effect), embedded anchor blocks as previously
25 discussed, and anchors, to mount a parapet to the printed concrete.


26 27 **5. Discussion**

28 The information presented in Table 1 points out that the number of realised large-scale construction
29 projects using digital fabrication techniques has surprisingly increased in the last two years. The
30 growing number and ambition of the DFC construction projects to be delivered in the near future
31 points out the urgent need for new, unified, and effective design-to-fabrication approaches [129, 28],
32 including the testing methods and regulations. Indeed, at the current stage of development, DFC
33 cannot sufficiently guarantee the product quality and design code compliance in many practical cases.
34 Understanding the structural engineering peculiarities of digitally fabricated load-bearing concrete
35 structures is rapidly becoming a priority for their safe use. However, when evaluating the potential of
36 structural engineering in DFC, a highly inter-linked scenario must be taken into account, as depicted
37 in Figure 17. In particular, for a given project, determining the relationships between material
38 performance (in either the fresh or the hardened state), DFC process adopted, pre-defined function,
39 reinforcement typology, and design aspects represents the major challenge thus far.

40 The examination of the projects reported in this review paper revealed that DFC by means of an
41 extrusion process is by a large margin the most widely used technique thus far for fabricating whole-
42 house systems as well as bridge structures or components; this circumstance can be explained by its
43 practical flexibility and process reliability for either off-site or on-site production, as well as by the

1 considerably larger research and development effort put into this technology with respect to other
 2 DFC processes.

3



4


5 Figure 17: Inter-linked aspects for the structural engineering of DFC structures.
 6

7 In terms of the target products of DFC, the fabrication of building systems represents the most
 8 frequent solution, mostly driven by the possibility of rapidly implementing construction projects and
 9 achieving affordable housing with unusual aesthetic properties. In most of these cases, the walls of
 10 the houses are fabricated by a continuous printing process, large-scale particle bed techniques or by
 11 assembling components consisting of concrete panels produced either off-site or on-site and then
 12 connected by means of conventional steel anchoring/connection systems (e.g. see Figure 18). From
 13 the structural point of view and for the design of these construction solutions, the realised houses
 14 resemble the behaviour of (unreinforced) masonry structures or that of an assembly of load-bearing
 15 walls subjected to vertical loads. Indeed, for a limited number of situations (e.g. based on the in-
 16 service conditions or the type of applied load), the requirement of tensile capacity and ductility can
 17 be over-ridden by designing structures loaded only in compression or with minimal levels of traction.
 18 This solution is reasonably feasible and easy to apply, as it does not require additional manufacturing
 19 steps to insert reinforcement while guaranteeing form freedom; however, note that unreinforced
 20 single curved walls (the standard case in the listed applications) could have been built cheaper by
 21 using other conventional techniques. Moreover, the fully structural characterisation of such types of
 22 structures is yet to be determined (e.g. in-plane/out-of-plane behaviour), particularly focusing on the
 23 mechanical role of the layer interfaces/bonds in such possible design approaches.

24 Design limitations and requirements should be carefully considered in reference to the risk of
 25 shrinkage cracks and tensile stresses induced by the imposed deformations, particularly involving
 26 support settlements and displacements. In this regard, the existing standards, such as EN 1996-1-2,

1 which deals with unreinforced masonry and reinforced masonry where the reinforcement is added to
2 provide ductility, strength, or improve serviceability, or EN 1992-1-1 for load-bearing walls, can
3 represent a possible inspiration for adapting the current available design. However, as these types of
4 structures are dependent on new material properties and DFC particularities, the principles and
5 application rules given in the mentioned standards may be not entirely applicable, needing to be
6 supplemented for instance by experimental validation.

7



8 Figure 18: Plan view of assembled DFC panels for housing: (a) 3D Housing 05 [74] and (b) 'the BOD' [75]
9

10 As far as infrastructure objects are concerned, the available literature reports that the most common
11 method to produce bridge structures involves digitally fabricating concrete segments by using an
12 extrusion process (with an almost free-form in the cross section) and then assembling them on-site
13 by means of post-tensioning in the direction of the stacked layers of concrete. This is somehow similar
14 to the already available technology on precast segmental bridges [130] regulated by the post-
15 tensioning design principles. The evaluation of the structural integrity of these types of structures
16 should be complemented by experimental validation (as described in *Subsection 4.1*) in the case that
17 provisions about minimum reinforcement are not fulfilled and/or problems of weak interfaces are
18 expected. For other bridge examples, obtained by a different DFC process (e.g. particle bed 3d
19 printing fabricated by D-shape in eight segments using a micro-reinforced concrete), there was not
20 enough documentation to be discussed in this paper.

21 On the structural element scale, in addition to some research works and practical cases demonstrating
22 the high potential for the structural implementation of beams, columns, etc. (e.g. [45, 94, 131, 132]),
23 temporary projects have normally been classified as artworks (e.g. KnitCandela) and, for this reason,
24 did not require strict structural design regulations.

1 In general, given that the applied design methodologies are in the early stages of development and
2 are still evolving, the following common features characterising construction projects developed thus
3 far can be pointed out:

- 4
- 5 - The reference lifetime for structural design input is relatively short, probably because of the
6 insufficient knowledge on the durability behaviour of innovative DFC products (e.g. five-year
7 reference lifetime).
- 8 - The structural design is frequently reliant on experimental inputs from the researchers from
9 academia (particularly for DFC material property inputs).
- 10 - The fact that different available structural design codes allow exceptions in reference to
11 innovative construction products/systems (provided that they are well founded theoretically
12 or experimentally) is exploited. For instance, in the case of reinforced concrete structures, the
13 design loads can be taken from EN 1991 [91, 92], while the input material properties and
14 checking criteria can be derived from experimental testing; the corresponding design values
15 can be determined, for instance, according to EN 1990, Annex D. Moreover, note that the
16 safety factor commonly used to calculate the design concrete compressive strength has been
17 increased in some cases to account for the larger scatter in the mechanical properties of
18 digitally fabricated concrete.
- 19 - Even though EN 1990 Annex D adequately covers the engineering issues for construction and
20 first service, for cyclic loading in brittle DFC objects/components (particularly in the cases of
21 weak layer interfaces), long-term performance needs to be evaluated with respect to the crack
22 propagation phenomena over time.
- 23 - Ensuring of the concrete cover dimensions depends on the specific DFC technique adopted
24 and can be achieved within the printed layer itself, by appropriately filling the hollow-printed
25 objects/components or by covering a pre-arranged steel reinforcing system.
- 26 - In unreinforced DFC products, structural design provisions are mostly used to verify the
27 structural integrity in terms of the maximum and minimum concrete stresses as well as the
28 maximum allowable deflections. For DFC structures containing reinforcement, all the design
29 provisions concerning the composite action of the concrete and the reinforcement should be
30 considered as well.
- 31 - Unreinforced digitally fabricated products are dimensioned in a way that they do not exceed
32 the design concrete tensile strength. Therefore, they are typically restricted to applications
33 with very low structural demands, such as the vertical walls of a single-storey building.
- 34 - The mechanical issues of component joining from prefabricated components are still mostly
35 not yet addressed, particularly with respect to the print inaccuracy, roughness, and stress
36 concentrations.
- 37 - Classical approaches for the simulation of the behaviour of structural elements are only
38 suitable for simple 1D or 2D geometries. The simulation of all the complex shapes enabled
39 by DFC processes requires detailed numerical modelling using either linear or non-linear
40 material models for the structural calculations.

41

42 In terms of the envisioned opportunities to exploit the benefits of DFC, topology optimisation
43 procedures certainly represent the most promising approach because of the high compatibility with
44 the free-form fabrication approach. Indeed, through the preventive choice of a reference mechanical
45 model and constraint conditions, the shape of a structural element can be tailored with reference to

1 the applied loads and/or the allowable deformations. However, it is clear that the design conceived in
2 this way is currently too demanding for topology optimisation procedures, as their level of
3 development is still not sufficient to deal with the particularities of DFC techniques or reinforcing
4 strategies. In some cases, DFC can also be used to control concrete cracking as well as to provide
5 additional opportunities related to the saving of structural reinforcing steel.

6

7 **6. CONCLUSIONS**

8 In this paper, we discussed the recent construction projects carried out by means of DFC technologies.
9 The focus was on the aspects of structural design and engineering of DFC with a major emphasis on
10 extrusion-based concrete 3D printing, as it is one of the most widely used and documented DFC
11 technologies thus far.

12 Depending on the specific DFC process adopted, the structural use of DFC products requires
13 appropriate attention throughout the project, from the design, to the analysis, production, execution,
14 assembly, experimental validation, and in-service use. Progress has been made in this sense,
15 particularly for the general approval of construction projects as well as for the code compliance of
16 DFC products; this has been possible mainly because of the fact that different available structural
17 design codes allow exceptions on the condition that appropriate experimental testing is used for
18 validation. Different international working committees are also active on these topics, and practical
19 standards/guidelines are expected to be released in the coming years to foster the widespread use of
20 these technologies. However, it is clear that a considerable amount of research needs to be performed
21 to consider DFC as a standard construction method. One of the priorities is represented by the
22 definition of appropriate parameters for the extensive concrete material characterisation to be used as
23 input in the structural design. The development of suitable numerical modelling approaches is also
24 desired in order to achieve further improvements on the topology/functional/structural optimisation
25 capabilities of DFC. The application of reinforcement is still scarcely compatible with DFC processes
26 because of geometrical complexities, uncertainties regarding the reinforcement-to-matrix bond, and
27 the integration of the application of reinforcement bars in the printing process. This circumstance has
28 limited the structural design as well, thus requiring a considerable amount of research effort on this
29 topic.

30

31 **ACKNOWLEDGEMENTS**

32 Dr. Mata-Falcón and Prof. Kaufmann would like to thank the Swiss National Science Foundation for
33 support of most ETH-based work reported in this paper, along with partial financial support for Dr.
34 Mata-Falcón (National Centre for Competence in Research in Digital Fabrication in Architecture:
35 project number 51NF40_141853).

36 The authors would like to thank Hans Laagland of Witteveen+Bos consulting engineers for his
37 availability and for providing valuable comments in relation to DFC completed projects.

38

39 **REFERENCES**

40 [1] H. Van Damme, Concrete material science: Past, present, and future innovations, Cem.

- 1 Concr. Res. 112 (2018) 5–24. <https://doi.org/10.1016/j.cemconres.2018.05.002>.
- 2 [2] G. De Schutter, K. Lesage, V. Mechtcherine, V.N. Nerella, G. Habert, I. Agusti-Juan, Vision
3 of 3D printing with concrete — Technical, economic and environmental potentials, *Cem.*
4 *Concr. Res.* 112 (2018) 25–36. <https://doi.org/10.1016/j.cemconres.2018.06.001>.
- 5 [3] N. Gershenfeld, How to Make Almost Anything: The Digital Fabrication Revolution,
6 *Foreign Aff.* 91 (2012).
7 [https://heinonline.org/HOL/Page?handle=hein.journals/fora91&id=1077&div=114&collectio](https://heinonline.org/HOL/Page?handle=hein.journals/fora91&id=1077&div=114&collection=journals)
8 [n=journals](https://heinonline.org/HOL/Page?handle=hein.journals/fora91&id=1077&div=114&collection=journals) (accessed January 6, 2020).
- 9 [4] L. Sass, M. Botha, The Instant House: A Model of Design Production with Digital
10 Fabrication, *Int. J. Archit. Comput.* 4 (2006) 109–123.
11 <https://doi.org/10.1260/147807706779399015>.
- 12 [5] E. Lloret, A.R. Shahab, M. Linus, R.J. Flatt, F. Gramazio, M. Kohler, S. Langenberg,
13 Complex concrete structures: Merging existing techniques with digital fabrication, *Comput.*
14 *Des.* 60 (2015) 40–49. <http://dx.doi.org/10.1016/j.cad.2014.02.011> (accessed May 11, 2018).
- 15 [6] N. Ham, S. Lee, Project Benefits of Digital Fabrication in Irregular-Shaped Buildings, *Adv.*
16 *Civ. Eng.* 2019 (2019). <https://doi.org/10.1155/2019/3721397>.
- 17 [7] P. Wu, J. Wang, X. Wang, A critical review of the use of 3-D printing in the construction
18 industry, *Autom. Constr.* 68 (2016) 21–31. <https://doi.org/10.1016/j.autcon.2016.04.005>.
- 19 [8] I. Agustí-Juan, F. Müller, N. Hack, T. Wangler, G. Habert, Potential benefits of digital
20 fabrication for complex structures: Environmental assessment of a robotically fabricated
21 concrete wall, *J. Clean. Prod.* 154 (2017) 330–340.
22 <https://doi.org/10.1016/j.jclepro.2017.04.002>.
- 23 [9] S.C. Paul, G.P.A.G. van Zijl, I. Gibson, A review of 3D concrete printing systems and
24 materials properties: current status and future research prospects, *Rapid Prototyp. J.* 24
25 (2018) 784–798. <https://doi.org/10.1108/RPJ-09-2016-0154>.
- 26 [10] I. Gibson, D.W. Rosen, B. Stucker, Additive manufacturing technologies: Rapid prototyping
27 to direct digital manufacturing, Springer US, 2010. [https://doi.org/10.1007/978-1-4419-1120-](https://doi.org/10.1007/978-1-4419-1120-9)
28 [9](https://doi.org/10.1007/978-1-4419-1120-9).
- 29 [11] J.L. Jewett, J. V. Carstensen, Experimental investigation of strut-and-tie layouts in deep RC
30 beams designed with hybrid bi-linear topology optimization, *Eng. Struct.* 197 (2019).
31 <https://doi.org/10.1016/j.engstruct.2019.109322>.
- 32 [12] A. Søndergaard, O. Amir, P. Eversmann, L. Piskorec, F. Stan, F. Gramazio, M. Kohler,
33 Topology Optimization and Robotic Fabrication of Advanced Timber Space-Frame
34 Structures, in: *Robot. Fabr. Archit. Art Des.* 2016, Springer International Publishing, 2016:
35 pp. 190–203. https://doi.org/10.1007/978-3-319-26378-6_14.
- 36 [13] J. Schwartz, Graphic statics and their potential for digital design and fabrication with
37 concrete, *Cem. Concr. Res.* 112 (2018) 122–135.
38 <https://doi.org/10.1016/j.cemconres.2018.06.015>.
- 39 [14] Y.W.D. Tay, B. Panda, S.C. Paul, N.A. Noor Mohamed, M.J. Tan, K.F. Leong, 3D printing
40 trends in building and construction industry: a review, *Virtual Phys. Prototyp.* 12 (2017)
41 261–276. <https://doi.org/10.1080/17452759.2017.1326724>.
- 42 [15] G. Vantighem, V. Boel, W. De Corte, M. Steeman, Compliance, stress-based and multi-
43 physics topology optimization for 3D-printed concrete structures, in: *RILEM Bookseries*,

- 1 Springer Netherlands, 2019: pp. 323–332. https://doi.org/10.1007/978-3-319-99519-9_30.
- 2 [16] D.D. Camacho, P. Clayton, W. O’Brien, R. Ferron, M. Juenger, S. Salamone, C. Seepersad,
3 Applications of additive manufacturing in the construction industry - A prospective review,
4 in: ISARC 2017 - Proc. 34th Int. Symp. Autom. Robot. Constr., International Association for
5 Automation and Robotics in Construction I.A.A.R.C), 2017: pp. 246–253.
6 <https://doi.org/10.22260/isarc2017/0033>.
- 7 [17] I. Agustí-Juan, G. Habert, Environmental design guidelines for digital fabrication, *J. Clean.*
8 *Prod.* 142 (2017) 2780–2791. <https://doi.org/10.1016/j.jclepro.2016.10.190>.
- 9 [18] Infrastructure productivity: How to save \$1 trillion a year | McKinsey, (n.d.).
10 [https://www.mckinsey.com/industries/capital-projects-and-infrastructure/our-](https://www.mckinsey.com/industries/capital-projects-and-infrastructure/our-insights/infrastructure-productivity)
11 [insights/infrastructure-productivity](https://www.mckinsey.com/industries/capital-projects-and-infrastructure/our-insights/infrastructure-productivity) (accessed January 3, 2020).
- 12 [19] 2020 Engineering and Construction Industry Trends | Deloitte US, (n.d.).
13 [https://www2.deloitte.com/us/en/pages/energy-and-resources/articles/engineering-and-](https://www2.deloitte.com/us/en/pages/energy-and-resources/articles/engineering-and-construction-industry-trends.html)
14 [construction-industry-trends.html](https://www2.deloitte.com/us/en/pages/energy-and-resources/articles/engineering-and-construction-industry-trends.html) (accessed January 2, 2020).
- 15 [20] G. Austern, I.G. Capeluto, Y.J. Grobman, Rationalization methods in computer aided
16 fabrication: A critical review, *Autom. Constr.* 90 (2018) 281–293.
17 <https://doi.org/10.1016/j.autcon.2017.12.027>.
- 18 [21] A. Paolini, S. Kollmannsberger, E. Rank, Additive manufacturing in construction: A review
19 on processes, applications, and digital planning methods, *Addit. Manuf.* 30 (2019).
20 <https://doi.org/10.1016/j.addma.2019.100894>.
- 21 [22] C. Robeller, A. Stitic, P. Mayencourt, Y. Weinand, Interlocking Folded Plate: Integrated
22 Mechanical Attachment for Structural Wood Panels, in: *Adv. Archit. Geom. 2014*, Springer
23 International Publishing, Cham, 2015: pp. 281–294. [https://doi.org/10.1007/978-3-319-](https://doi.org/10.1007/978-3-319-11418-7_18)
24 [11418-7_18](https://doi.org/10.1007/978-3-319-11418-7_18).
- 25 [23] A. Menges, T. Schwinn, O.D. Krieg, *Advancing wood architecture: A computational*
26 *approach*, Taylor and Francis, 2016. <https://doi.org/10.4324/9781315678825>.
- 27 [24] J. Willmann, M. Knauss, T. Bonwetsch, A.A. Apolinarska, F. Gramazio, M. Kohler, Robotic
28 timber construction - Expanding additive fabrication to new dimensions, *Autom. Constr.* 61
29 (2016) 16–23. <https://doi.org/10.1016/j.autcon.2015.09.011>.
- 30 [25] Amsterdam 3D printed steel bridge - Arup, (n.d.). [https://www.arup.com/projects/mx3d-](https://www.arup.com/projects/mx3d-bridge)
31 [bridge](https://www.arup.com/projects/mx3d-bridge) (accessed January 2, 2020).
- 32 [26] Printing a stainless steel bridge: An exploration of structural properties of stainless steel
33 additive manufactures for civil engineering purposes | TU Delft Repositories, (n.d.).
34 [https://repository.tudelft.nl/islandora/object/uuid:b4286867-9c1c-40c1-a738-](https://repository.tudelft.nl/islandora/object/uuid:b4286867-9c1c-40c1-a738-cf28dd7b6de5?collection=education)
35 [cf28dd7b6de5?collection=education](https://repository.tudelft.nl/islandora/object/uuid:b4286867-9c1c-40c1-a738-cf28dd7b6de5?collection=education) (accessed January 2, 2020).
- 36 [27] R. Duballet, O. Baverel, J. Dirrenberger, Classification of building systems for concrete 3D
37 printing, *Autom. Constr.* 83 (2017) 247–258. <https://doi.org/10.1016/j.autcon.2017.08.018>.
- 38 [28] T. Wangler, N. Roussel, F.P. Bos, T.A.M. Salet, R.J. Flatt, Digital Concrete: A Review,
39 *Cem. Concr. Res.* 123 (2019). <https://doi.org/10.1016/j.cemconres.2019.105780>.
- 40 [29] R. Buswell, Digital Fabrication with Concrete: Process Classification and Description, *Cem.*
41 *Concr. Res.* (2020).
- 42 [30] C. Gosselin, R. Duballet, P. Roux, N. Gaudillière, J. Dirrenberger, P. Morel, Large-scale 3D
43 printing of ultra-high performance concrete - a new processing route for architects and

- 1 builders, *Mater. Des.* 100 (2016) 102–109. <https://doi.org/10.1016/j.matdes.2016.03.097>.
- 2 [31] V. Mechtcherine, V.N. Nerella, F. Will, M. Näther, J. Otto, M. Krause, Large-scale digital
3 concrete construction – CONPrint3D concept for on-site, monolithic 3D-printing, *Autom.*
4 *Constr.* 107 (2019). <https://doi.org/10.1016/j.autcon.2019.102933>.
- 5 [32] B. Khoshnevis, Automated construction by contour crafting - Related robotics and
6 information technologies, in: *Autom. Constr.*, 2004: pp. 5–19.
7 <https://doi.org/10.1016/j.autcon.2003.08.012>.
- 8 [33] R.A. Buswell, W.R. Leal de Silva, S.Z. Jones, J. Dirrenberger, 3D printing using concrete
9 extrusion: A roadmap for research, *Cem. Concr. Res.* 112 (2018) 37–49.
10 <https://doi.org/10.1016/j.cemconres.2018.05.006>.
- 11 [34] G. Vantyghem, W. De Corte, E. Shakour, O. Amir, 3D printing of a post-tensioned concrete
12 girder designed by topology optimization, *Autom. Constr.* 112 (2020) 103084.
13 <https://doi.org/10.1016/j.autcon.2020.103084>.
- 14 [35] M. Popescu, L. Reiter, A. Liew, T. Van Mele, R.J. Flatt, P. Block, Building in Concrete with
15 an Ultra-lightweight Knitted Stay-in-place Formwork: Prototype of a Concrete Shell Bridge,
16 *Structures.* 14 (2018) 322–332. <https://doi.org/10.1016/j.istruc.2018.03.001>.
- 17 [36] E. Lloret, A.R. Shahab, M. Linus, R.J. Flatt, F. Gramazio, M. Kohler, S. Langenberg,
18 Complex concrete structures: Merging existing casting techniques with digital fabrication,
19 *CAD Comput. Aided Des.* 60 (2015) 40–49. <https://doi.org/10.1016/j.cad.2014.02.011>.
- 20 [37] E. Lloret-Fritschi, F. Scotto, F. Gramazio, M. Kohler, K. Graser, T. Wangler, L. Reiter, R.J.
21 Flatt, J. Mata-Falcón, Challenges of real-scale production with smart dynamic casting, in:
22 RILEM Bookseries, Springer Netherlands, 2019: pp. 299–310. https://doi.org/10.1007/978-3-319-99519-9_28.
- 24 [38] D. Lowke, E. Dini, A. Perrot, D. Weger, C. Gehlen, B. Dillenburger, Particle-bed 3D printing
25 in concrete construction – Possibilities and challenges, *Cem. Concr. Res.* 112 (2018) 50–65.
26 <https://doi.org/10.1016/j.cemconres.2018.05.018>.
- 27 [39] P. Ayres, W.R. Leal da Silva, P. Nicholas, T.J. Andersen, J.P.R. Greisen, SCRIM – Sparse
28 Concrete Reinforcement in Meshworks, in: *Robot. Fabr. Archit. Art Des. 2018*, Springer
29 International Publishing, 2019: pp. 207–220. https://doi.org/10.1007/978-3-319-92294-2_16.
- 30 [40] H. Lindemann, R. Gerbers, S. Ibrahim, F. Dietrich, E. Herrmann, K. Dröder, A. Raatz, H.
31 Kloft, Development of a shotcrete 3D-printing (SC3DP) technology for additive
32 manufacturing of reinforced freeform concrete structures, in: RILEM Bookseries, Springer
33 Netherlands, 2019: pp. 287–298. https://doi.org/10.1007/978-3-319-99519-9_27.
- 34 [41] B. Khoshnevis, D. Hwang, K.-T. Yao, Z. Yah, Mega-scale fabrication by contour crafting,
35 *Int. J. Ind. Syst. Eng.* 1 (2006) 301–320. <https://doi.org/10.1504/IJISE.2006.009791>.
- 36 [42] N. Hack, K. Doerfler, R. Flatt, A. Walzer, T. Wangler, H. Heller, J. Mata-Falcón, N. Kumar,
37 M. Lussi, K. Graser, T. Sandy, J. Buchli, W. Kaufmann, F. Gramazio, M. Kohler, Mesh
38 Mould - A structural stay-in-place formwork system for robotic in situ fabrication of non-
39 standard concrete structures: A real scale architectural demonstrator, *Autom. Constr.* (n.d.).
- 40 [43] T.A.M. Salet, Z.Y. Ahmed, F.P. Bos, H.L.M. Laagland, Design of a 3D printed concrete
41 bridge by testing, *Virtual Phys. Prototyp.* 13 (2018) 222–236.
42 <https://doi.org/10.1080/17452759.2018.1476064>.
- 43 [44] B. García de Soto, I. Agustí-Juan, J. Hunhevicz, S. Joss, K. Graser, G. Habert, B.T. Adey,

- 1 Productivity of digital fabrication in construction: Cost and time analysis of a robotically
2 built wall, *Autom. Constr.* 92 (2018) 297–311. <https://doi.org/10.1016/j.autcon.2018.04.004>.
- 3 [45] A. Bhardwaj, S.Z. Jones, N. Kalantar, Z. Pei, J. Vickers, T. Wangler, P. Zavattieri, N. Zou,
4 Additive Manufacturing Processes for Infrastructure Construction: A Review, *J. Manuf. Sci.*
5 *Eng.* 141 (2019). <https://doi.org/10.1115/1.4044106>.
- 6 [46] A. Jipa, F. Giacomarra, R. Giesecke, G. Chousou, M. Pacher, B. Dillenburger, M. Lomaglio,
7 M. Leschok, 3D-printed formwork for bespoke concrete stairs from computational design to
8 digital fabrication, in: *Proc. SCF 2019 - ACM Symp. Comput. Fabr.*, Association for
9 Computing Machinery, Inc, 2019. <https://doi.org/10.1145/3328939.3329003>.
- 10 [47] B. Khoshnevis, X. Yuan, B. Zahiri, J. Zhang, B. Xia, Construction by contour crafting using
11 sulfur concrete with planetary applications, in: *Rapid Prototyp. J.*, Emerald Group Publishing
12 Ltd., 2016: pp. 848–856. <https://doi.org/10.1108/RPJ-11-2015-0165>.
- 13 [48] J. Mata-Falcón, P. Bischof, W. Kaufmann, Exploiting the potential of digital fabrication for
14 sustainable and economic concrete structures, in: *RILEM Bookseries*, Springer Netherlands,
15 2019: pp. 157–166. https://doi.org/10.1007/978-3-319-99519-9_14.
- 16 [49] L. Reiter, T. Wangler, N. Roussel, R.J. Flatt, The role of early age structural build-up in
17 digital fabrication with concrete, *Cem. Concr. Res.* 112 (2018) 86–95.
18 <https://doi.org/10.1016/j.cemconres.2018.05.011>.
- 19 [50] N. Roussel, Rheological requirements for printable concretes, *Cem. Concr. Res.* (2018) (this
20 issue).
- 21 [51] R.J. et al. Flatt, Setting on demand for digital concrete: principles, measurements, chemistry
22 and validation, *Cem. Concr. Res.* (2020).
- 23 [52] B. Panda, S. Chandra Paul, M. Jen Tan, Anisotropic mechanical performance of 3D printed
24 fiber reinforced sustainable construction material, *Mater. Lett.* 209 (2017) 146–149.
25 <https://doi.org/10.1016/J.MATLET.2017.07.123>.
- 26 [53] R.J.M. Wolfs, F.P. Bos, T.A.M. Salet, Hardened properties of 3D printed concrete: The
27 influence of process parameters on interlayer adhesion, *Cem. Concr. Res.* 119 (2019) 132–
28 140. <https://doi.org/10.1016/j.cemconres.2019.02.017>.
- 29 [54] D. Asprone, C. Menna, F.P. Bos, T.A.M. Salet, J. Mata-Falcón, W. Kaufmann, Rethinking
30 reinforcement for digital fabrication with concrete, *Cem. Concr. Res.* 112 (2018) 111–121.
31 <https://doi.org/10.1016/j.cemconres.2018.05.020>.
- 32 [55] B. Khoshnevis, R. Russell, H. Kwon, S. Bukkapatnam, Crafting large prototypes, *IEEE*
33 *Robot. Autom. Mag.* 8 (2001) 33–42. <https://doi.org/10.1109/100.956812>.
- 34 [56] S. Lim, T. Le, J. Webster, R. Buswell, S. Austin, A. Gibb, T. Thorpe, Fabricating
35 construction components using layer manufacturing technology, (2009).
- 36 [57] 3D Castle Completed, (n.d.). <http://www.totalkustom.com/3d-castle-completed.html>
37 (accessed January 19, 2020).
- 38 [58] Viliaprint, vers l’impression 3D de maisons à Reims - 3Dnatives, (n.d.).
39 <https://www.3dnatives.com/viliaprint-impression-3d-maison-22012019/> (accessed January
40 19, 2020).
- 41 [59] G+7 Apartment Complex — CyBe Construction, (n.d.). [https://cybe.eu/case/g7-apartment-](https://cybe.eu/case/g7-apartment-complex/)
42 [complex/](https://cybe.eu/case/g7-apartment-complex/) (accessed January 19, 2020).

- 1 [60] Milestone in Eindhoven door Houben / Van Mierlo Architecten - De Architect, (n.d.).
2 [https://www.dearchitect.nl/techniek/artikel/2019/01/milestone-in-eindhoven-door-houben-](https://www.dearchitect.nl/techniek/artikel/2019/01/milestone-in-eindhoven-door-houben-van-mierlo-architecten-101204066?vakmedianet-approve-cookies=1&_ga=2.204634195.2115172256.1578950705-118263712.1557759491)
3 [van-mierlo-architecten-101204066?vakmedianet-approve-](https://www.dearchitect.nl/techniek/artikel/2019/01/milestone-in-eindhoven-door-houben-van-mierlo-architecten-101204066?vakmedianet-approve-cookies=1&_ga=2.204634195.2115172256.1578950705-118263712.1557759491)
4 [cookies=1&_ga=2.204634195.2115172256.1578950705-118263712.1557759491](https://www.dearchitect.nl/techniek/artikel/2019/01/milestone-in-eindhoven-door-houben-van-mierlo-architecten-101204066?vakmedianet-approve-cookies=1&_ga=2.204634195.2115172256.1578950705-118263712.1557759491) (accessed
5 January 19, 2020).
- 6 [61] D. Asprone, Structural design and testing of digital fabrication concrete structures, in:
7 RILEM Bookseries - Chapter 6, 2020: p. To be published.
- 8 [62] 3D Concrete Printing - Most Promising Projects | All3DP, (n.d.). [https://all3dp.com/2/3d-](https://all3dp.com/2/3d-concrete-printing-most-promising-projects/)
9 [concrete-printing-most-promising-projects/](https://all3dp.com/2/3d-concrete-printing-most-promising-projects/) (accessed January 9, 2020).
- 10 [63] 3D Printing as a Construction Process for Structural Members, (n.d.).
11 http://ijsrd.com/C_Article.php?manuscript=HABTP003 (accessed January 9, 2020).
- 12 [64] M. Sakin, Y.C. Kiroglu, 3D Printing of Buildings: Construction of the Sustainable Houses of
13 the Future by BIM, in: Energy Procedia, Elsevier Ltd, 2017: pp. 702–711.
14 <https://doi.org/10.1016/j.egypro.2017.09.562>.
- 15 [65] The 3D Printed Office of the Future - ASME, (n.d.). [https://www.asme.org/topics-](https://www.asme.org/topics-resources/content/3d-printed-office-the-future)
16 [resources/content/3d-printed-office-the-future](https://www.asme.org/topics-resources/content/3d-printed-office-the-future) (accessed January 9, 2020).
- 17 [66] Complex concrete column made using 3D printed formwork - MaterialDistrict, (n.d.).
18 <https://materialdistrict.com/article/complex-concrete-column-3d-printed-formwork/>
19 (accessed January 9, 2020).
- 20 [67] Vertical Modulations: computational design for concrete 3D printed columns - dbt, (n.d.).
21 [http://dbt.arch.ethz.ch/publication/vertical-modulations-computational-design-for-concrete-](http://dbt.arch.ethz.ch/publication/vertical-modulations-computational-design-for-concrete-3d-printed-columns/)
22 [3d-printed-columns/](http://dbt.arch.ethz.ch/publication/vertical-modulations-computational-design-for-concrete-3d-printed-columns/) (accessed January 9, 2020).
- 23 [68] CyBe Construction Announces That 3D Printing is Complete for Dubai’s R&Drone
24 Laboratory - 3DPrint.com | The Voice of 3D Printing / Additive Manufacturing, (n.d.).
25 <https://3dprint.com/176561/cybe-3d-printed-dubai-laboratory/> (accessed January 9, 2020).
- 26 [69] 3D printed bridge - IAAC, (n.d.). <https://iaac.net/project/3d-printed-bridge/> (accessed
27 January 9, 2020).
- 28 [70] T.A.M. Salet, Z.Y. Ahmed, F.P. Bos, H.L.M. Laagland, Design of a 3D printed concrete
29 bridge by testing, Virtual Phys. Prototyp. 13 (2018) 222–236.
30 <https://doi.org/10.1080/17452759.2018.1476064>.
- 31 [71] World’s First 3D Printed Bicycle Bridge Opens in the Netherlands | All3DP, (n.d.).
32 <https://all3dp.com/worlds-first-3d-printed-bicycle-bridge-opens-in-netherlands/> (accessed
33 January 9, 2020).
- 34 [72] PROJECTS – Yrys Concept House | XtreeE, (n.d.). [http://www.xtreee.eu/projects-yrys-](http://www.xtreee.eu/projects-yrys-concept-house/)
35 [concept-house/](http://www.xtreee.eu/projects-yrys-concept-house/) (accessed January 9, 2020).
- 36 [73] J. Kidwell, Best Practices and Applications of 3D Printing in the Construction Industry, n.d.
- 37 [74] 3dhousing05 - Massimiliano Locatelli | CLS ARCHITETTI, (n.d.).
38 <https://www.3dhousing05.com/> (accessed January 9, 2020).
- 39 [75] 3D Printing Completed on 3D Printhuset’s Building On Demand - 3DPrint.com | The Voice
40 of 3D Printing / Additive Manufacturing, (n.d.). [https://3dprint.com/195020/3d-printhuset-](https://3dprint.com/195020/3d-printhuset-building-on-demand/)
41 [building-on-demand/](https://3dprint.com/195020/3d-printhuset-building-on-demand/) (accessed January 9, 2020).
- 42 [76] T. Wangler, Digital Concrete: Research and Applications, Proc. 10th Int. Concr. Congr.

- 1 (2019) 2–12.
- 2 [77] Tsinghua University News, (n.d.).
3 https://news.tsinghua.edu.cn/publish/thunews/en/9670/2019/20190116161602224500923/20190116161602224500923_.html (accessed January 9, 2020).
- 4
5 [78] Swiss Researchers Begin Construction of the DFAB HOUSE | All3DP, (n.d.).
6 <https://all3dp.com/swiss-researchers-begin-construction-dfab-house/> (accessed January 9,
7 2020).
- 8 [79] ETH Zurich and NCCR DFAB’s monolithic columns present new tectonics of concrete
9 printed architecture, (n.d.). [https://worldarchitecture.org/article-links/ecgcf/eth-zurich-and-](https://worldarchitecture.org/article-links/ecgcf/eth-zurich-and-nccr-dfab-s-monolithic-columns-present-new-tectonics-of-concrete-printed-architecture.html)
10 [nccr-dfab-s-monolithic-columns-present-new-tectonics-of-concrete-printed-architecture.html](https://worldarchitecture.org/article-links/ecgcf/eth-zurich-and-nccr-dfab-s-monolithic-columns-present-new-tectonics-of-concrete-printed-architecture.html)
11 (accessed January 9, 2020).
- 12 [80] Construction of first 3D-printed building to start | De Ingenieur, (n.d.).
13 <https://www.deingenieur.nl/artikel/construction-of-first-3d-printed-building-to-start>
14 (accessed January 9, 2020).
- 15 [81] F.P.B. G. Grasser, L. Pammer, H. Köll, E. Werner, Complex architecture in printed concrete:
16 the case of the Innsbruck University 350th anniversary pavilion Cohesion, in: Digit. Concr.
17 2020, 2nd RILEM Int. Conf. Concr. Digit. Fabr., 2020: p. Submitted.
- 18 [82] Dubai is now home to the largest 3D-printed building in the world - Business Insider, (n.d.).
19 [https://www.businessinsider.com/dubai-largest-3d-printed-building-apis-cor-photos-2019-](https://www.businessinsider.com/dubai-largest-3d-printed-building-apis-cor-photos-2019-12?international=true&r=US&IR=T)
20 [12?international=true&r=US&IR=T](https://www.businessinsider.com/dubai-largest-3d-printed-building-apis-cor-photos-2019-12?international=true&r=US&IR=T) (accessed January 9, 2020).
- 21 [83] ICON + New Story + ECHALE Unveil First Homes in 3D-Printed Community | ICON,
22 (n.d.). <https://www.iconbuild.com/updates/first-3d-printed-home-community> (accessed
23 January 9, 2020).
- 24 [84] DFAB HOUSE – Building with robots and 3D printers, (n.d.). <https://dfabhouse.ch/>
25 (accessed January 8, 2020).
- 26 [85] SPATIAL TIMBER ASSEMBLIES – DFAB HOUSE, (n.d.).
27 https://dfabhouse.ch/spatial_timber_assemblies/ (accessed January 8, 2020).
- 28 [86] LIGHTWEIGHT TRANSLUCENT FAÇADE – DFAB HOUSE, (n.d.).
29 <https://dfabhouse.ch/lightweight-translucent-facade/> (accessed January 8, 2020).
- 30 [87] Swiss Society of Engineers and Architects (SIA), SIA Code 260 for Basis of Structural
31 Design, (2013).
- 32 [88] Swiss Society of Engineers and Architects (SIA), SIA Code 261 for Actions on Structures,
33 (2014).
- 34 [89] Swiss Society of Engineers and Architects (SIA), SIA Code 262 for Concrete Structures,
35 (2013).
- 36 [90] E. Lloret-Fritschi, T. Wangler, L. Gebhard, J. Mata-Falcón, S. Mantellato, F. Scotto, J.
37 Burger, A. Szabo, N. Ruffray, L. Reiter, F. Boscaro, W. Kaufmann, M. Kohler, F. Gramazio,
38 R.J. Flatt, From Smart Dynamic Casting to a growing family of Digital Casting Systems,
39 Cem. Concr. Res. (2020).
- 40 [91] A. Jipa, A. Meibodi, R. Giesecke, D. Shammas, M. Bernhard, B. Dillenburger, 3D-Printed
41 Formwork for Prefabricated Concrete Slabs, in: 1st Int. Conf. 3D Constr. Print., Melbourne,
42 Australia, 2018.

- 1 [92] N. Hack, T. Wangler, J. Mata-Falcón, K. Dörfler, N. Kumar, A. Walzer, K. Graser, L. Reiter,
2 H. Richner, J. Buchli, W. Kaufmann, R. Flatt, F. Gramazio, M. Kohler, Mesh Mould: An on
3 site on site, robotically fabricated, functional formwork, in: Proceedings Second Concr.
4 Innovalon Conf. (2nd CIC), Tromsø, Norway, 2017: p. 10.
- 5 [93] K. Dörfler, N. Hack, T. Sandy, M. Giftthaler, M. Lussi, A.N. Walzer, J. Buchli, F. Gramazio,
6 M. Kohler, Mobile robotic fabrication beyond factory conditions: case study Mesh Mould
7 wall of the DFAB HOUSE, *Constr. Robot.* (2019). [https://doi.org/10.1007/s41693-019-](https://doi.org/10.1007/s41693-019-00020-w)
8 00020-w.
- 9 [94] Report GHA Future Tree :: Basler & Hofmann, (n.d.).
10 [https://www.baslerhofmann.ch/en/news/individuelle-newseintraege/report-gha-future-](https://www.baslerhofmann.ch/en/news/individuelle-newseintraege/report-gha-future-tree.html)
11 [tree.html](https://www.baslerhofmann.ch/en/news/individuelle-newseintraege/report-gha-future-tree.html) (accessed January 8, 2020).
- 12 [95] J. Burger, E. Lloret-Fritsch, F. Scotto, T. Demoulin, L. Gebhard, J. Mata-Falcón, F.
13 Gramazio, M. Kohler, R.J. Flatt, Eggshell: Ultra-thin 3D Printed Formwork for Concrete
14 Structures, *3D Print. Addit. Manuf.* (2019) Submitted.
- 15 [96] M. Popescu, M. Rippmann, A. Liew, L. Reiter, R.J. Flatt, T. Van Mele, P. Block, Structural
16 design, digital fabrication and construction of the cable-net and knitted formwork of the
17 KnitCandela concrete shell, *Structures.* (2019) Submitted.
- 18 [97] T.A.M. Salet, Z.Y. Ahmed, F.P. Bos, H.L.M. Laagland, 3D printed concrete bridge, in: *Proc.*
19 *Int. Conf. Prog. Addit. Manuf., Pro-AM*, 2018: pp. 2–9. <https://doi.org/10.25341/D4530C>.
- 20 [98] EN 1991-1-1: Eurocode 1: Actions on structures - Part 1-1: General actions - Densities, self-
21 weight, imposed loads for buildings, 1991.
- 22 [99] EN 1991-1-2: Eurocode 1: Actions on structures - Part 1-2: General actions - Actions on
23 structures exposed to fire, 1991.
- 24 [100] EN 1990: Eurocode - Basis of structural design, 2002.
- 25 [101] F. Bos, Z. Ahmed, E. Jutinov, T. Salet, Experimental Exploration of Metal Cable as
26 Reinforcement in 3D Printed Concrete, *Materials* (Basel). 10 (2017) 1314.
27 <https://doi.org/10.3390/ma10111314>.
- 28 [102] F.P. Bos, Z.Y. Ahmed, R.J.M. Wolfs, T.A.M. Salet, 3D printing concrete with reinforcement,
29 in: *High Tech Concr. Where Technol. Eng. Meet - Proc. 2017 Fib Symp.*, Springer
30 International Publishing, 2017: pp. 2484–2493. [https://doi.org/10.1007/978-3-319-59471-](https://doi.org/10.1007/978-3-319-59471-2_283)
31 2_283.
- 32 [103] O. Amir, E. Shakour, Simultaneous shape and topology optimization of prestressed concrete
33 beams, *Struct. Multidiscip. Optim.* 57 (2018) 1831–1843. [https://doi.org/10.1007/s00158-](https://doi.org/10.1007/s00158-017-1855-5)
34 017-1855-5.
- 35 [104] M. Bogomolny, O. Amir, Conceptual design of reinforced concrete structures using topology
36 optimization with elastoplastic material modeling, *Int. J. Numer. Methods Eng.* 90 (2012)
37 1578–1597. <https://doi.org/10.1002/nme.4253>.
- 38 [105] Y. Luo, Z. Kang, Layout design of reinforced concrete structures using two-material
39 topology optimization with Drucker-Prager yield constraints, *Struct. Multidiscip. Optim.* 47
40 (2013) 95–110. <https://doi.org/10.1007/s00158-012-0809-1>.
- 41 [106] Y. Luo, M.Y. Wang, M. Zhou, Z. Deng, Topology optimization of reinforced concrete
42 structures considering control of shrinkage and strength failure, *Comput. Struct.* 157 (2015)
43 31–41. <https://doi.org/10.1016/j.compstruc.2015.05.009>.

- 1 [107] T. Pastore, V. Mercuri, C. Menna, D. Asprone, P. Festa, F. Auricchio, Topology optimization
2 of stress-constrained structural elements using risk-factor approach, *Comput. Struct.* 224
3 (2019). <https://doi.org/10.1016/j.compstruc.2019.106104>.
- 4 [108] A.T. Gaynor, J.K. Guest, C.D. Moen, Reinforced Concrete Force Visualization and Design
5 Using Bilinear Truss-Continuum Topology Optimization, *J. Struct. Eng.* 139 (2013) 607–
6 618. [https://doi.org/10.1061/\(ASCE\)ST.1943-541X.0000692](https://doi.org/10.1061/(ASCE)ST.1943-541X.0000692).
- 7 [109] O. Amir, A topology optimization procedure for reinforced concrete structures, *Comput.*
8 *Struct.* 114–115 (2013) 46–58. <https://doi.org/10.1016/j.compstruc.2012.10.011>.
- 9 [110] M. Bruggi, A numerical method to generate optimal load paths in plain and reinforced
10 concrete structures, *Comput. Struct.* 170 (2016) 26–36.
11 <https://doi.org/10.1016/j.compstruc.2016.03.012>.
- 12 [111] J. Liu, A.T. Gaynor, S. Chen, Z. Kang, K. Suresh, A. Takezawa, L. Li, J. Kato, J. Tang,
13 C.C.L. Wang, L. Cheng, X. Liang, A.C. To, Current and future trends in topology
14 optimization for additive manufacturing, *Struct. Multidiscip. Optim.* 57 (2018) 2457–2483.
15 <https://doi.org/10.1007/s00158-018-1994-3>.
- 16 [112] A.T. Gaynor, J.K. Guest, Topology optimization considering overhang constraints:
17 Eliminating sacrificial support material in additive manufacturing through design, *Struct.*
18 *Multidiscip. Optim.* 54 (2016) 1157–1172. <https://doi.org/10.1007/s00158-016-1551-x>.
- 19 [113] M. Langelaar, An additive manufacturing filter for topology optimization of print-ready
20 designs, *Struct. Multidiscip. Optim.* 55 (2017) 871–883. <https://doi.org/10.1007/s00158-016-1522-2>.
- 21
22 [114] P. Zhang, J. Liu, A.C. To, Role of anisotropic properties on topology optimization of additive
23 manufactured load bearing structures, *Scr. Mater.* 135 (2017) 148–152.
24 <https://doi.org/10.1016/j.scriptamat.2016.10.021>.
- 25 [115] C. Dapogny, R. Estevez, A. Faure, G. Michailidis, Shape and topology optimization
26 considering anisotropic features induced by additive manufacturing processes, *Comput.*
27 *Methods Appl. Mech. Eng.* 344 (2019) 626–665. <https://doi.org/10.1016/j.cma.2018.09.036>.
- 28 [116] G. Vantighem, W. De Corte, M. Steeman, V. Boel, Density-based topology optimization for
29 3D-printable building structures, *Struct. Multidiscip. Optim.* (2019).
30 <https://doi.org/10.1007/s00158-019-02330-7>.
- 31 [117] G. Vantighem, V. Boel, M. Steeman, W. De Corte, Multi-material topology optimization
32 involving simultaneous structural and thermal analyses, *Struct. Multidiscip. Optim.* 59
33 (2019) 731–743. <https://doi.org/10.1007/s00158-018-2095-z>.
- 34 [118] A.S.J. Suiker, Mechanical performance of wall structures in 3D printing processes: Theory,
35 design tools and experiments, *Int. J. Mech. Sci.* 137 (2018) 145–170.
36 <https://doi.org/10.1016/j.ijmecsci.2018.01.010>.
- 37 [119] R.J.M. Wolfs, F.P. Bos, T.A.M. Salet, Early age mechanical behaviour of 3D printed
38 concrete: Numerical modelling and experimental testing, *Cem. Concr. Res.* 106 (2018) 103–
39 116. <https://doi.org/10.1016/j.cemconres.2018.02.001>.
- 40 [120] T. Salet, F. Bos, R. Wolfs, Z. Ahmed, 3D concrete printing—a structural engineering
41 perspective, *High Tech Concr. Where Technol. Eng. Meet.* (2018).
42 [http://fibsymposium2017.com/wp-content/uploads/2017/06/3D-Concrete-printing-prof-Theo-](http://fibsymposium2017.com/wp-content/uploads/2017/06/3D-Concrete-printing-prof-Theo-Salet-webversion.pdf)
43 [Salet-webversion.pdf](http://fibsymposium2017.com/wp-content/uploads/2017/06/3D-Concrete-printing-prof-Theo-Salet-webversion.pdf) (accessed May 13, 2018).

- 1 [121] J. Kruger, S. Zeranka, G. van Zijl, 3D concrete printing: A lower bound analytical model for
2 buildability performance quantification, *Autom. Constr.* 106 (2019).
3 <https://doi.org/10.1016/j.autcon.2019.102904>.
- 4 [122] Particle Finite Element Simulation of Extrusion Processes of Fresh Concrete During 3D
5 Concrete-Printing | Request PDF, (n.d.).
6 [https://www.researchgate.net/publication/336719530_Particle_Finite_Element_Simulation_o
7 f_Extrusion_Processes_of_Fresh_Concrete_During_3D_Concrete-Printing](https://www.researchgate.net/publication/336719530_Particle_Finite_Element_Simulation_of_Extrusion_Processes_of_Fresh_Concrete_During_3D_Concrete-Printing) (accessed January
8 8, 2020).
- 9 [123] P. Steadman, Why are most buildings rectangular?, *Archit. Res. Q.* 10 (2006) 119–130.
10 <https://doi.org/10.1017/S1359135506000200>.
- 11 [124] A.N. R. Ammann, Behaviour of RC members with weak layer interfaces in tension, Institut
12 für Baustatik und Konstruktion, ETH Zurich, 2018.
- 13 [125] ISO - ISO 22966:2009 - Execution of concrete structures, (n.d.).
14 <https://www.iso.org/standard/41262.html> (accessed January 9, 2020).
- 15 [126] EN 1992-1-1: Eurocode 2: Design of concrete structures - Part 1-1: General rules and rules
16 for buildings, 2004.
- 17 [127] BSI, Execution of concrete structures, British Standards Limited, 2009.
18 <http://www.cscses.com/uploads/2016328/20160328110518251825.pdf> (accessed January 9,
19 2020).
- 20 [128] BS EN 206:2013+A1:2016 Concrete. Specification, performance, production and
21 conformity, (n.d.). <https://shop.bsigroup.com/ProductDetail/?pid=000000000030326195>
22 (accessed January 9, 2020).
- 23 [129] O. Davtalab, A. Kazemian, B. Khoshnevis, Perspectives on a BIM-integrated software
24 platform for robotic construction through Contour Crafting, *Autom. Constr.* 89 (2018) 13–23.
25 <https://doi.org/10.1016/j.autcon.2018.01.006>.
- 26 [130] International Federation for Structural Concrete. Task Group 1.7 “Construction of Precast
27 Segmental Bridges,” *Precast segmental bridges : guide to good practice*, n.d.
- 28 [131] S. Lim, T. Le, J. Webster, R. Buswell, S. Austin, A. Gibb, T. Thorpe, Fabricating
29 Construction Components Using Layered Manufacturing Technology, *Glob. Innov. Constr.*
30 *Conf.* 2009. (2009) 512–520. <https://doi.org/10.1016/j.autcon.2011.06.010>.
- 31 [132] D. Asprone, F. Auricchio, C. Menna, V. Mercuri, 3D printing of reinforced concrete
32 elements: Technology and design approach, *Constr. Build. Mater.* 165 (2018).
33 <https://doi.org/10.1016/j.conbuildmat.2018.01.018>.

34

35